

2.0 PROJECT DESCRIPTION

Keystone proposes to construct, operate, maintain, inspect, and monitor a pipeline system that would transport crude oil from its existing facilities in Hardisty, Alberta, Canada to delivery points at Cushing, Oklahoma and in Texas. This section describes Keystone's proposed action and includes the following information:

- Overview of the Proposed Project (Section 2.1);
- Aboveground Facilities (Section 2.2);
- Project Design and Construction Procedures (Section 2.3);
- Operations and Maintenance (Section 2.4);
- Connected Actions (Section 2.5); and
- Future Plans and Decommissioning (Section 2.6).

Information presented in this EIS on the proposed Project was obtained from documents submitted to DOS by Keystone, including the following primary sources:

- Keystone's application for a Presidential Permit;
- Keystone's Environmental Report (ER), attachments to the ER, and related supplemental filings;
- Keystone's General Conformity Determination; and
- Keystone's responses to DOS data requests.

The EIS includes basic graphics depicting key aspects of the proposed Project; more detailed alignment sheets are available at the DOS website for the proposed Project at: <http://www.keystonepipeline-xl.state.gov/clientsite/kestonexl.nsf?Open>. To access the documents, click on "Project Documents" then "Supplemental Filing."

In addition to the proposed Project, this EIS describes and addresses the impacts of four actions that are separate from the proposed Project and are not part of the Presidential Permit application submitted by Keystone. Those actions have been determined to be connected actions for the purposes of this NEPA review as defined by 40 CFR 1508.25(a)(1) and are described in Section 2.5.

2.1 OVERVIEW OF THE PROPOSED PROJECT

The proposed Project would have the initial capacity to deliver up to 700,000 bpd of WCSB crude oil from the proposed Canada-U.S. border crossing to delivery points in Cushing, Oklahoma, in Nederland, Texas (near Port Arthur), and in Moore Junction, Texas (east of Houston). Keystone currently has binding commitments to ship 380,000 bpd of Canadian crude oil. The proposed Project could transport up to 830,000 bpd of crude oil by adding pumping capacity if warranted by future market demand.

At the time of publication of the draft EIS, Keystone had applied to the PHMSA for consideration of a Special Permit request to operate the proposed Project at a slightly higher pressure than would be allowed using the standard design factor in the regulations. That would have resulted in a maximum crude oil throughput of approximately 900,000 bpd. DOS worked with PHMSA to develop Project-specific

Special Conditions that would have been incorporated into the Special Permit. On August 5, 2010, Keystone withdrew its application to PHMSA for a Special Permit. To enhance the overall safety of the proposed Project, DOS and PHMSA continued working on Special Conditions specific to the proposed Project and ultimately established 57 Project-specific Special Conditions. As a result, Keystone agreed to design, construct, operate, maintain, and monitor the proposed Project in accordance with the regulatory requirements in 49 CFR Parts 194 and 195 as well as the more stringent set of 57 Project-specific Special Conditions developed by PHMSA presented in Appendix U. As a result, the maximum throughput of the proposed Project decreased and is currently proposed to be approximately 830,000 bpd. In addition, the maximum operating pressure would be reduced from the requested 1,400 psig to 1,308 psig.

The proposed Project would deliver primarily WCSB crude oil (which would likely be heavy crude oil) based on current market forecasts, to three delivery points in the U.S. that in turn provide access to many other U.S. pipeline systems, terminals, and refineries. The ultimate destinations of the crude oil beyond these delivery points would not be contracted with Keystone and therefore are not considered part of the proposed Project.

The proposed Project includes three new pipeline segments in five states plus additional pumping capacity on the existing Cushing Extension of the Keystone Oil Pipeline Project (See Figures 2.1-1 through 2.1-6). The proposed new pipeline segments are:

- The Steele City Segment (from near Morgan, Montana to Steele City, Nebraska) – the southern end of this segment would connect to the northern end of the existing Cushing Extension near Steele City;
- The Gulf Coast Segment (from Cushing, Oklahoma to Nederland, Texas) – the northern end of this segment would connect to the southern end of the Cushing Extension at the Cushing tank farm; and
- The Houston Lateral (from the Gulf Coast Segment, in Liberty County, Texas to Moore Junction, in Harris County, Texas).

The actual alignment continues to undergo small revisions based on ongoing landowner negotiations and regulatory/resource agency input. The analysis in the EIS is based on the alignment as of March 26, 2010, which used an approximate total pipeline length of 1,384 miles. As of June 10, 2011, these small alignment revisions have increased the total pipeline miles by approximately 3 along the entire alignment. For completeness, Table 2.1-1 has been revised to show the small alignment revisions in mileage by state as of June 10, 2011 as well as the mileage by state as of March 26, 2010. The alignment and resulting mileage will continue to be adjusted as landowner and agency input is addressed prior to proposed Project implementation. Approximately 1,387 linear miles of proposed new pipeline would be located in five states as listed in Table 2.1-1.

Segment	State	June 10, 2011 New Pipeline Miles ^a	June 10, 2011 Mileposts (From – To) ^b	March 26, 2010 New Pipeline Miles ^a	March 26, 2010 Mileposts (From – To) ^b
Steele City Segment	Montana	284.2	0-284.2	282.7	0-282.7
	South Dakota	314.8	284.2-599.0	314.2	282.7-596.8
	Nebraska	254.8	599.0-853.8	254.7	596.8-851.6
Steele City Total		853.8	-	851.6	-

TABLE 2.1-1 Miles of New Pipe by State					
Segment	State	June 10, 2011 New Pipeline Miles^a	June 10, 2011 Mileposts (From – To)^b	March 26, 2010 New Pipeline Miles^a	March 26, 2010 Mileposts (From – To)^b
Keystone Cushing Extension	Nebraska	0	N/A	0	N/A
	Kansas	0	N/A	0	N/A
	Oklahoma	0	N/A	0	N/A
Gulf Coast Segment	Oklahoma	155.9	0-155.9	155.7	0-155.7
	Texas	328.4	155.9-484.3	328.1	155.7-483.8
Gulf Coast Total		484.3	-	483.8	-
Houston Lateral	Texas	48.6	0-48.6	48.6	0-48.6
Project Total		1,386.7	-	1,383.9	-

^a Mileages are approximate and subject to change based on final approved design and routing.

^b Mileposting for each segment of the proposed Project starts at 0.0 at the northernmost point of each segment and increases in the direction of oil flow.

The proposed Project would include 30 new pump stations, mainline valves (MLVs) at the pump stations, 112 MLVs along the proposed pipeline (termed “intermediate” MLVs) based on current information, a tank farm at Cushing, Oklahoma that would be a delivery point, one delivery point with a surge relief system that includes two surge relief tanks at Nederland, and an oil delivery point and a surge relief system without tanks at Moore Junction. These facilities are listed in Table 2.1-2 and are described in more detail in Section 2.2.

Access roads, pipe stockpile sites, railroad sidings, and construction camps would also be required during construction of the proposed Project. Electric power lines and associated facility upgrades would be constructed, as required, by local providers to supply electrical power for the proposed new pump stations and remotely operated valves and densitometers¹ located along the pipeline route. Local power providers would be responsible for obtaining the necessary approvals or authorizations from federal, state, and local governments for such facilities. Although the permitting process for the electrical facilities is an independent process, the construction and operation of these facilities are considered connected actions under NEPA. Therefore, the potential impacts of the facilities were preliminarily evaluated as a part of the NEPA environmental review described in this EIS based on currently available information.

TABLE 2.1-2 Ancillary Facilities by State		
Segment	State	Ancillary Facilities
Steele City Segment	Montana	6 New Pump Stations
		21 Intermediate Mainline Valves (MLVs)
		50 Access Roads

¹ A densitometer is an on-line and continuous use device used to measure the density of a flowing stream. In the oil and gas industry, a densitometer is normally used to measure the density of liquid hydrocarbon. The measurement of density is used to determine the quantity of crude oil passing through a meter.

**TABLE 2.1-2
Ancillary Facilities by State**

Segment	State	Ancillary Facilities
	South Dakota	7 New Pump Stations 17 Intermediate MLVs 18 Access Roads
	Nebraska	5 New Pump Stations 19 Intermediate MLVs 12 Access Roads
Keystone Cushing Extension	Kansas	2 New Pump Stations 1 Access Road
Gulf Coast Segment	Oklahoma	Cushing Tank Farm 4 New Pump Stations 15 Intermediate MLVs 76 Access Roads
	Texas	6 New Pump Stations 32 Intermediate MLVs 157 Access Roads 1 Delivery Site
Houston Lateral	Texas	8 Intermediate MLVs 1 Delivery Site 31 Access Roads

Additionally, the Western Area Power Administration (Western) has determined that due to load demands at proposed pump stations in South Dakota when the proposed Project is at or near maximum throughput, a new 230-kilovolt (kV) transmission line approximately 70 miles long (the proposed Big Bend to Witten electrical transmission line)² would need to be added to the existing electrical grid system to ensure system reliability.

Construction would require a 110-foot wide construction right-of-way (ROW) in most areas, pipe stockpile sites, construction yards, railroad sidings, and construction camps. A 50-foot-wide ROW would be maintained along the proposed route during operation.

Keystone has Project commitments to transport approximately 600,000 bpd of crude oil, including firm contracts to transport 380,000 bpd of WCSB crude oil to existing PADD III delivery points. Keystone also has firm contracts to transport 155,000 bpd of WCSB crude oil to Cushing in its existing Keystone Oil Pipeline Project, which includes the Keystone Mainline and the Keystone Cushing Extension. If the proposed Project is approved and implemented, Keystone would transfer shipment of crude oil under those contracts to the proposed Project. In addition, the proposed Project has firm commitments to transport approximately 65,000 bpd of crude oil, and could ship up to 100,000 bpd of crude oil, delivered to the proposed Project through the planned Keystone Market Link, LLC. Bakken Marketlink Project. The proposed Project may also transport up to 150,000 bpd of crude oil delivered to the proposed Project

² In the draft EIS the facility now known as the Big Bend to Witten 230-kV transmission line was named the Lower Brule to Witten 230-kV transmission line.

through the planned Keystone Marketlink, LLC. Cushing Marketlink Project (both projects are considered connected actions as defined by CEQ and are described in Section 2.5).

The proposed Project is planned to be in service in 2013, with the actual date dependant on receipt of all necessary permits, approvals, and authorizations.

As noted in Section 1.1, the proposed Project would primarily deliver WCSB crude oil, which would likely be heavy crude oil based on current market forecasts, to three delivery points in the U.S. that in turn provide access to many other U.S. pipeline systems and terminals. The ultimate destinations of the crude oil beyond these delivery points would not be contracted with Keystone and are not a part of the proposed Project.

2.1.1 Proposed Route Segments

2.1.1.1 Steele City Segment

A total of approximately 852 miles of new pipeline would be constructed for the Steele City Segment. Approximately 30 miles (4 percent) of the alignment would be within approximately 300 feet of currently existing pipelines, utilities, or ROWs. The remaining 822 miles (96 percent) of the route would be new ROW. Eighteen new pump stations would be constructed and operated on land parcels ranging in area from 5 to 15 acres. New electrical distribution lines would be constructed and operated by local power providers to service the pump stations. Those facilities are considered connected actions for the purposes of this EIS and are described in Section 2.5.

A total of approximately 14,875 acres of lands would be affected during construction of the Steele City Segment. Of this acreage, approximately 5,344 acres would be permanent ROW during operation.

2.1.1.2 Cushing Extension (New Pump Stations)

Two new pump stations would be constructed in Kansas along the existing Keystone Cushing Extension. These pump stations would enable the proposed Project to maintain the pressure required to make crude oil deliveries at the desired throughput volumes. The two new pump stations would disturb a total of approximately 15 acres of land during both construction and operation of the proposed Project.

2.1.1.3 Gulf Coast Segment and Houston Lateral

A total of approximately 484 miles of new pipeline would be constructed along the Gulf Coast Segment. Approximately 393 miles (82 percent) would be within approximately 300 feet of existing pipelines, utilities, or road ROWs. The remaining 87 miles (18 percent) of the route would be in new ROWs. The Houston Lateral would be approximately 49 miles long, 20 miles (41 percent) of which would be within approximately 300 feet of existing pipelines, utilities, or road ROWs. The remaining 29 miles (59 percent) would be in a new ROW. Approximately 8,542 acres of land would be affected during construction of the Gulf Coast and Houston Lateral segments combined. Of this, 3,121 acres would be permanent ROW during Project operation.

Keystone would also construct a tank farm on an approximately 74-acre site at Cushing (see Section 2.2.6). Ten new pump stations would be constructed and operated on the Gulf Coast Segment. Nine of the pump stations would be on land parcels ranging in area from 5 to 15 acres. Pump station 32 would be constructed within the boundaries of the tank farm. Keystone would also install two delivery facilities, one at Nederland and one at Moore Junction, Texas. At Nederland, the proposed Project would include construction and operation of two surge relief tanks (a primary tank and a backup tank). Each tank would

have a capacity of approximately 10,417 barrels (435,514 gallons) with two carbon adsorption beds each, in series. One tank would be on line at all times and the second would be on standby to be able to direct crude oil in the proposed pipeline into one of the tanks to relieve pressure on the system during surge events. Although the actual number of surge relief events that could occur during proposed Project operations is not known, it was assumed that there would be an average of one surge relief event per month for a total of 12 surge relief events per year (see Section 2.12 for additional information on the surge relief system).

2.1.2 Land and Borrow Material Requirements

2.1.2.1 Land Requirements

Construction of the proposed Project would require a 110-foot-wide construction ROW. In certain sensitive areas, which may include wetlands, cultural sites, shelterbelts, residential areas, or commercial/industrial areas, the construction ROW would be reduced to 85 feet except in South Dakota where it would be reduced to a 75-foot width unless the USACE requires an 85-foot width.

Figure 2.1.2-1 illustrates typical construction areas along the ROW where the route would not parallel an existing pipeline corridor or another linear facility. Figures 2.1.2-2 and 2.1.2-3 illustrate typical construction areas where the pipeline would parallel an existing linear feature.

Approximately 24,134 acres of land would be disturbed during construction. The areas of surface disturbance due to construction and operation of the proposed Project are listed in Table 2.1.2-1.

After construction, the temporary ROW (15,341 acres) would be restored consistent with applicable federal and state regulations and permits, the easement agreements negotiated between Keystone and individual landowners or land managers, and the construction methods and environmental protection procedures described in the Keystone Construction, Mitigation, and Reclamation (CMR) plan (presented in Appendix B and described in Section 2.3). Those measures would be incorporated into the proposed Project to reduce the potential impacts of construction.

The permanent ROW would have an area of approximately 8,793 acres; of that total, 292 acres would be the area of pump stations, valves, and other aboveground facilities. The permanent ROW would also be restored as described above and to allow access to the ROW for the life of the proposed Project to support surface and aerial inspections and any repairs or maintenance as necessary.

Segment/State	Facility	Area Affected (Acres) ^a	
		Construction ^b	Operation ^c
Steele City Segment			
Montana	Pipeline ROW	3,758.6	1,713.2
	Additional Temporary Workspace Areas	327.8	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	460.7	0.0
	Construction Camps	182.5	0.0
	Pump Stations and Delivery Facilities	50.1	50.1
	Access Roads ^d	266.5	21.7
Montana Subtotal		5,046.3	1,785.0

**TABLE 2.1.2-1
Summary of Lands Affected**

Segment/State	Facility	Area Affected (Acres) ^a	
		Construction ^b	Operation ^c
South Dakota	Pipeline ROW	4,178.9	1,904.0
	Additional Temporary Workspace Areas	309.3	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	581.2	0.0
	Construction Camps	160.2	0.0
	Pump Stations/Delivery Facilities	59.4	59.4
	Access Roads ^d	144.8	9.1
South Dakota Subtotal		5,433.7	1,972.5
Nebraska	Pipeline ROW	3,384.8	1,543.8
	Additional Temporary Workspace Areas	349.5	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	515.6	0.0
	Pump Stations and Delivery Facilities	42.2	42.2
	Access Roads ^d	53.3	0.0
Nebraska Subtotal		4,345.3	1,586.1
Steele City Subtotal		14,875.3	5,343.5
Keystone Cushing Extension			
Kansas	Pipeline ROW	0.0	0.0
	Additional Temporary Workspace Areas	0.0	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	0.0	0.0
	Pump Stations and Delivery Facilities	15.2	15.2
	Access Roads ^d	0.0	0.0
Kansas Subtotal		15.2	15.2
Keystone Cushing Extension Subtotal		15.2	15.2
Gulf Coast Segment			
Oklahoma	Pipeline ROW	2,033.5	943.8
	Additional Temporary Workspace Areas	179.1	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	701.3	0.0
	Tank Farm, Pump Stations, and Delivery Facilities	74.1	74.1
	Access Roads ^d	118.6	15.1
Oklahoma Subtotal		3,106.6	1,033.1
Texas	Pipeline ROW	4,198.8	1,988.9
	Additional Temporary Workspace Areas	332.6	0.0
	Pipe Stockpile Sites, Rail Sidings, and Contractor Yards	519.6	0.0
	Pump Stations and /Delivery Facilities ^e	51.1	51.1
	Access Roads	333.6	48.1
Texas Subtotal		5,435.8	2,088.1
Gulf Coast Subtotal		8,542.4	3,121.1

TABLE 2.1.2-1 Summary of Lands Affected			
Segment/State	Facility	Area Affected (Acres)^a	
		Construction^b	Operation^c
Houston Lateral	Pipeline ROW	652	294
	Additional Temporary Workspace Areas	32	0
	Pipe Storage Sites, Rail Sidings, and Contractor Yards	5	0
	Access Roads ^d	62	19
Houston Lateral Subtotal		751	313
Project Total		24,133.9	8,792.8

^a Areas listed do not include the electrical distribution lines required for the pump stations. Information on the electrical distribution lines is presented in Section 2.5.

^b Area calculated based on a 110-foot-wide construction ROW except in certain wetlands, cultural sites, shelterbelts, residential areas, and commercial/industrial areas where an 85-foot-wide construction ROW would be used, or in areas requiring extra width for workspace necessitated by site conditions.

^c Area calculated based on a 50-foot-wide permanent ROW. All pigging facilities would be located within either pump stations or delivery facility sites. Intermediate MLVs and densitometers would be within the permanent ROW.

^d Access road area calculated based on 30-foot width.

^e Keystone would install two 10,417-barrel surge tanks at the terminus of the Gulf Coast Segment on previously disturbed land.

2.1.2.2 Borrow Material Requirements

Borrow material would be required for temporary sites (such as storage sites, contractor yards, temporary access roads, and access pads at ROW road crossings), to stabilize the land for permanent facilities (including pump stations, valve sites, and permanent access roads), and for padding the bottom of the pipeline trench in some areas. All gravel and other borrow material would be obtained from existing, previously permitted commercial sources located as close to the pipe or contractor yards as possible.

Generally, about 7,000 cubic yards of gravel would be required for each pipe storage site and about 4,600 cubic yards of gravel would be required for each contractor yard. The approximately 400 temporary access roads would be graveled, as would access pads at ROW crossings of public and private roads. Approximately 1,590 such road crossings are proposed. The 50 permanent access roads would also be graveled. About 6 inches of gravel would typically be used at pump stations and MLV sites. Along portions of the route, the trench bottom would be filled with padding material such as sand or gravel, to protect the pipeline coating.

Table 2.1.2-2 lists the approximate amount of borrow material that would be required in each state, and Table 2.1.2-3 lists the borrow material required for each facility type. Keystone would conduct detailed surveys of pipe storage sites, railroad sidings, and contractor yards prior to construction to determine the exact amounts of borrow material that would be required for each site.

TABLE 2.1.2-2 Borrow Material Requirements by State	
State	Cubic Yards of Material
Montana	152,531
South Dakota	142,122
Nebraska	108,935
Kansas ^a	12,000
Oklahoma	144,402
Texas ^b	298,412
Total	858,402

^a Borrow material required for the two proposed pump stations on the Keystone Cushing Extension.

^b Includes a portion of the Gulf Coast Segment and the Houston Lateral.

TABLE 2.1.2-3 Borrow Material Requirements by Facility Type	
Facility Type	Cubic Yards of Material
Pipe Storage Site	108,000
Contractor Yard	134,400
Temporary Access Roads	28,579
Access Pads for Road Crossings	37,860
Pump Stations	180,000
Valve Sites	2,812
Permanent Access Roads	242,970
Trench Bottom Padding ^a	85,000
Cushing Tank Farm	38,781
Total	858,402

^a Gravel may be replaced with sand or soil.

2.2 ABOVEGROUND FACILITIES

The proposed Project would require approximately 292 acres of land for aboveground facilities, including pump stations, delivery facilities, densitometer sites, intermediate MLVs, and the tank farm. During operations, Keystone would use standard agricultural herbicides to control the growth of vegetative species on all aboveground sites.

2.2.1 Pump Stations

A total of 30 new pump stations, each situated on an approximately 5- to 15-acre site, would be constructed; 18 would be in the Steele City Segment, 10 in the Gulf Coast Segment, and 2 along the existing Keystone Cushing Extension in Kansas. Keystone has proposed the pump station locations based on hydraulics analyses of the flow in the pipeline and other relevant variables. Figures 1.1-1 and 2.1-1 through 2.1-6 show the proposed locations of the pump stations. Table 2.2.1-1 lists the locations of the pump stations by milepost.

Each new pump station would consist of up to six pumps driven by electric motors, an electrical equipment shelter, a variable frequency drive equipment shelter, an electrical substation, 1 sump tank, 2 MLVs, a communication tower, a small maintenance and office building, and a parking area for station maintenance personnel. The electrical shelter would house the electrical systems and the communication and control equipment.

TABLE 2.2.1-1 Proposed Project Pump Station Locations			
Segment/State	Approximate Milepost	Segment/State	Approximate Milepost
Steele City Segment		Cushing Extension	
Montana		Kansas	
Pump Station 09	1.2	Pump Station 27	49.0
Pump Station 10	49.5	Pump Station 29	144.5
Pump Station 11	98.4	Gulf Coast Segment	
Pump Station 12	149.1	Oklahoma	
Pump Station 13	199.6	Pump Station 32	0.0
Pump Station 14	237.1	Pump Station 33	49.0
South Dakota		Pump Station 34	95.4
Pump Station 15	285.7	Pump Station 35	147.4
Pump Station 16	333.7	Texas	
Pump Station 17	387.4	Pump Station 40	380.5
Pump Station 18	440.2	Pump Station 41	435.2
Pump Station 19	496.1		
Pump Station 20	546.7		
Pump Station 21	591.9		
Nebraska			
Pump Station 22	642.4		
Pump Station 23	694.5		
Pump Station 24	751.7		
Pump Station 25	800.5		
Pump Station 26	851.3		

The pipe entering and exiting the pump station sites would be below grade. There would be an MLV installed on the entry pipe and on the exit pipe as required by 49 CFR 195.260 to allow isolation of the pump station equipment in the event of an emergency. The manifold connecting the pipeline to the equipment at each pump station would be aboveground and entirely within the pump station boundaries.

Down-lighting would be used at the pump stations wherever possible to minimize impacts to wildlife and would install a security fence around the entire pump station site. Inspection and maintenance personnel would access the pump stations through a gate that would be locked when no one is at the pump station.

The pump stations would operate on locally purchased electric power and would be fully automated for unmanned operation. If there is an electrical power outage, batteries would be used to maintain power to all communication and specific control equipment. Backup generators would not be installed at the pump

stations and therefore there would not be fuel storage tanks at the pump stations. Communication towers at pump stations generally would be approximately 33 feet high, but the antenna height at some pump stations may be greater based on final detailed engineering studies. In no event would antennae exceed a maximum height of 190 feet.

2.2.2 Mainline Valves

Keystone would install 112 intermediate MLVs along the proposed route and one MLV at each pump station. The intermediate MLVs would be installed within the permanent ROW. The intermediate MLVs would comprise:

- 17 manual mainline block valves;
- 24 check valves; and
- 71 remotely operated mainline block valves.

Block valves can block oil flow in both direction and divide up the pipeline into smaller segments that can be isolated to minimize and contain the effects of a line rupture. The block valves can be either manually or remotely operated. Check valves are designed to be held open by flowing oil and to close automatically when oil flow stops or is reversed. Each MLV would be within a fenced site that would be approximately 40 feet by 50 feet. Inspection and maintenance personnel would access the MLVs through a gate that would be locked when no one is at the MLV site.

EPA suggested considering the placement of additional intermediate mainline valves, particularly in areas of shallow groundwater and at river crossings of less than 100 feet where sensitive aquatic resources may exist. Remotely operated intermediate MLVs would be located at major river crossings, upstream of sensitive waterbodies, and at other locations required by 49 CFR 195.260 and as required by Special Condition 32 imposed by PHMSA and agreed to by Keystone (see Section 2.3.1 and Appendix U). Project-specific Special Condition 32 developed in consultation with PHMSA that Keystone agreed to incorporate into the proposed Project plan states:

“Keystone must design and install mainline block valves and check valves on the Keystone XL system based on the worst case discharge as calculated by 49 CFR § 194.105. Keystone shall locate valves in accordance with 49 CFR § 195.260 and by taking into consideration elevation, population, and environmentally sensitive locations, to minimize the consequences of a release from the pipeline. Mainline valves must be placed based on the analysis above or no more than twenty (20) miles apart, whichever is smaller.”

The requirement to take into consideration elevation, population, and environmentally sensitive locations to minimize consequences of a release, and the maximum valve spacing of 20 miles exceed what is currently required in 49 CFR § 195.260. Based on Special Condition 32, the proposed Project was redesigned to increase the number of intermediate mainline valves from 76 to 104 and some previously planned valve locations were moved. As per standard code requirements, there would also be two valves at each of the 30 pump stations.

Keystone would be able to operate the valves remotely to shut isolate a section of pipeline in the event of an emergency to minimize environmental impacts if an accidental release occurs. Mainline valves must be capable of closure at all times. Special Condition 32 also requires that the remotely operated valves must have remote power back-up to ensure communications are maintained during inclement weather. Each motor-operated valve station would include a diesel-fired emergency generator and a diesel fuel tank with secondary containment. Table 2.2.2-1 lists the locations of intermediate MLVs.

**TABLE 2.2.2-1
Intermediate Mainline Valve Locations**

Valve Tag	Type	Milepost	Segment^a
260-PHLPS-01A-B0-MLV-01	Motor Operated Valve	20.3	Steele City Segment
260-PHLPS-02A-B0-CKV-01	Check Valve	28.1	Steele City Segment
260-PHLPS-02A-B0-MLV-01	Manual Operated Valve	28.1	Steele City Segment
260-PHLPS-03A-B0-MLV-01	Motor Operated Valve	40.3	Steele City Segment
260-VLLEY-01A-B0-MLV-01	Motor Operated Valve	63.6	Steele City Segment
260-VLLEY-02A-B0-CKV-01	Check Valve	71.8	Steele City Segment
260-VLLEY-02A-B0-MLV-01	Manual Operated Valve	71.8	Steele City Segment
260-VLLEY-03A-B0-MLV-01	Motor Operated Valve	81.3	Steele City Segment
260-VLLEY-04A-B0-CKV-01	Check Valve	83.9	Steele City Segment
260-VLLEY-04A-B0-MLV-01	Manual Operated Valve	83.9	Steele City Segment
260-VLLEY-05A-B0-CKV-01	Check Valve	91.1	Steele City Segment
260-VLLEY-05A-B0-MLV-01	Manual Operated Valve	91.1	Steele City Segment
260-FTPCK-01A-B0-MLV-01	Motor Operated Valve	117.7	Steele City Segment
260-FTPCK-02A-B0-MLV-01	Motor Operated Valve	134.3	Steele City Segment
260-CRCLE-01B-B0-MLV-01	Motor Operated Valve	170.9	Steele City Segment
260-CRCLE-01A-B0-MLV-01	Motor Operated Valve	178.9	Steele City Segment
260-CRCLE-02A-B0-MLV-01	Motor Operated Valve	195.5	Steele City Segment
154-PRAIR-B0-CKV-0102	Check Valve	202.1	Steele City Segment
260-PRAIR-01A-B0-MLV-01	Motor Operated Valve	220.5	Steele City Segment
260-FALLN-01A-B0-MLV-01	Motor Operated Valve	245.9	Steele City Segment
260-FALLN-02A-B0-MLV-01	Motor Operated Valve	266.4	Steele City Segment
206-LKTLR-B0-CKV-0102	Check Valve	284.5	Steele City Segment
260-HRDNG-02A-B0-CKV-01	Check Valve	300.2	Steele City Segment
260-HRDNG-02A-B0-MLV-01	Motor Operated Valve	300.2	Steele City Segment
260-HRDNG-03A-B0-MLV-01	Motor Operated Valve	318.2	Steele City Segment
260-BFLPS-01B-B0-MLV-01	Motor Operated Valve	352.3	Steele City Segment
260-BFLPS-01A-B0-MLV-01	Motor Operated Valve	372.2	Steele City Segment
260-FAITH-01B-B0-MLV-01	Motor Operated Valve	407.3	Steele City Segment
260-FAITH-01A-B0-MLV-01	Motor Operated Valve	422.8	Steele City Segment
260-FAITH-02A-B0-CKV-01	Check Valve	434.1	Steele City Segment
260-FAITH-02A-B0-MLV-01	Manual Operated Valve	434.1	Steele City Segment
260-FAITH-03A-B0-MLV-01	Motor Operated Valve	460.1	Steele City Segment
260-HAKON-01A-B0-MLV-01	Motor Operated Valve	478.3	Steele City Segment
260-MURDO-01A-B0-MLV-01	Motor Operated Valve	515.7	Steele City Segment
260-MURDO-02A-B0-MLV-01	Motor Operated Valve	532.1	Steele City Segment
260-WINNR-01A-B0-MLV-01	Motor Operated Valve	566.5	Steele City Segment
260-WINNR-02A-B0-MLV-01	Motor Operated Valve	585.1	Steele City Segment
260-COLOM-01A-B0-MLV-01	Motor Operated Valve	599.0	Steele City Segment
260-COLOM-02A-B0-CKV-01	Check Valve	602.9	Steele City Segment
260-COLOM-02A-B0-MLV-01	Manual Operated Valve	602.9	Steele City Segment
260-COLOM-03A-B0-MLV-01	Motor Operated Valve	617.3	Steele City Segment

**TABLE 2.2.2-1
Intermediate Mainline Valve Locations**

Valve Tag	Type	Milepost	Segment^a
260-COLOM-04A-B0-CKV-01	Check Valve	619.7	Steele City Segment
260-COLOM-04A-B0-MLV-01	Manual Operated Valve	619.7	Steele City Segment
260-COLOM-05A-B0-MLV-01	Motor Operated Valve	637.1	Steele City Segment
260-ATKNS-01A-B0-MLV-01	Motor Operated Valve	663.5	Steele City Segment
260-ATKNS-01B-B0-MLV-01	Motor Operated Valve	681.6	Steele City Segment
260-ATKNS-02A-B0-MLV-01	Motor Operated Valve	714.5	Steele City Segment
260-ERCSN-01A-B0-MLV-01	Motor Operated Valve	735.1	Steele City Segment
260-ERCSN-02A-B0-CKV-01	Check Valve	749.5	Steele City Segment
260-ERCSN-02A-B0-MLV-01	Manual Operated Valve	749.5	Steele City Segment
260-CLCTY-01A-B0-CKV-01	Check Valve	767.1	Steele City Segment
260-CLCTY-01A-B0-MLV-01	Motor Operated Valve	767.1	Steele City Segment
260-CLCTY-02A-B0-MLV-01	Motor Operated Valve	774.3	Steele City Segment
260-CLCTY-03A-B0-CKV-01	Check Valve	792.6	Steele City Segment
260-CLCTY-03A-B0-MLV-01	Motor Operated Valve	792.6	Steele City Segment
260-EXETR-01A-B0-MLV-01	Motor Operated Valve	823.1	Steele City Segment
260-EXETR-02A-B0-MLV-01	Motor Operated Valve	839.9	Steele City Segment
290-CSHSP-01A-B0-MLV-01	Motor Operated Valve	17.8	Gulf Coast Segment
290-CSHSP-02A-B0-CKV-01	Check Valve	24.2	Gulf Coast Segment
290-CSHSP-02A-B0-MLV-01	Manual Operated Valve	24.2	Gulf Coast Segment
290-CSHSP-03A-B0-MLV-01	Motor Operated Valve	37.8	Gulf Coast Segment
290-CSHSP-04A-B0-CKV-01	Check Valve	40.6	Gulf Coast Segment
290-CSHSP-04A-B0-MLV-01	Manual Operated Valve	40.6	Gulf Coast Segment
290-CRMWL-01A-B0-MLV-01	Motor Operated Valve	66.7	Gulf Coast Segment
290-CRMWL-02A-B0-MLV-01	Motor Operated Valve	73.5	Gulf Coast Segment
290-CRMWL-03A-B0-MLV-01	Motor Operated Valve	77.5	Gulf Coast Segment
290-CRMWL-03A-B0-CKV-01	Check Valve	77.5	Gulf Coast Segment
290-TPELO-01A-B0-MLV-01	Motor Operated Valve	106.4	Gulf Coast Segment
290-TPELO-02A-B0-MLV-01	Motor Operated Valve	125.5	Gulf Coast Segment
290-TPELO-03A-B0-CKV-01	Check Valve	128.9	Gulf Coast Segment
290-TPELO-03A-B0-MLV-01	Motor Operated Valve	128.9	Gulf Coast Segment
290-BRYAN-01A-B0-MLV-01	Motor Operated Valve	151.0	Gulf Coast Segment
290-BRYAN-02A-B0-MLV-01	Manual Operated Valve	162.6	Gulf Coast Segment
290-BRYAN-02A-B0-CKV-01	Check Valve	162.6	Gulf Coast Segment
290-BRYAN-02B-B0-MLV-01	Motor Operated Valve	170.0	Gulf Coast Segment
290-BRYAN-03A-B0-MLV-01	Motor Operated Valve	188.9	Gulf Coast Segment
290-BRYAN-04A-B0-MLV-01	Manual Operated Valve	192.4	Gulf Coast Segment
290-BRYAN-04A-B0-CKV-01	Check Valve	192.4	Gulf Coast Segment
290-DELTA-01A-B0-MLV-01	Motor Operated Valve	200.6	Gulf Coast Segment
290-DELTA-02A-B0-MLV-01	Manual Operated Valve	203.1	Gulf Coast Segment
290-DELTA-02A-B0-CKV-01	Check Valve	203.1	Gulf Coast Segment
290-DELTA-03A-B0-MLV-01	Motor Operated Valve	220.3	Gulf Coast Segment

**TABLE 2.2.2-1
Intermediate Mainline Valve Locations**

Valve Tag	Type	Milepost	Segment^a
290-DELTA-04A-B0-MLV-01	Motor Operated Valve	233.6	Gulf Coast Segment
290-WNSBR-01B-B0-MLV-01	Motor Operated Valve	252.5	Gulf Coast Segment
290-WNSBR-01A-B0-MLV-01	Motor Operated Valve	262.4	Gulf Coast Segment
290-WNSBR-02A-B0-MLV-01	Manual Operated Valve	267.7	Gulf Coast Segment
290-WNSBR-02A-B0-CKV-01	Check Valve	267.7	Gulf Coast Segment
290-WNSBR-03A-B0-MLV-01	Motor Operated Valve	277.7	Gulf Coast Segment
290-LKTLR-01A-B0-MLV-01	Motor Operated Valve	299.8	Gulf Coast Segment
290-LKTLR-02A-B0-MLV-01	Motor Operated Valve	315.2	Gulf Coast Segment
290-LKTLR-03A-B0-MLV-01	Motor Operated Valve	330.5	Gulf Coast Segment
290-LUFKN-01B-B0-MLV-01	Motor Operated Valve	349.8	Gulf Coast Segment
290-LUFKN-01A-B0-MLV-01	Motor Operated Valve	365.9	Gulf Coast Segment
290-LUFKN-02A-B0-MLV-01	Manual Operated Valve	371.6	Gulf Coast Segment
290-LUFKN-02A-B0-CKV-01	Check Valve	371.6	Gulf Coast Segment
290-CORGN-01B-B0-MLV-01	Motor Operated Valve	400.7	Gulf Coast Segment
290-CORGN-01A-B0-MLV-01	Motor Operated Valve	408.7	Gulf Coast Segment
290-CORGN-02A-B0-MLV-01	Motor Operated Valve	420.4	Gulf Coast Segment
290-CORGN-03A-B0-MLV-01	Motor Operated Valve	430.2	Gulf Coast Segment
290-LIBRT-01A-B0-MLV-01	Motor Operated Valve	448.8	Gulf Coast Segment
290-LIBRT-02A-B0-MLV-01	Motor Operated Valve	454.8	Gulf Coast Segment
290-LIBRT-03A-B0-MLV-01	Motor Operated Valve	462.5	Gulf Coast Segment
290-LIBRT-04A-B0-MLV-01	Motor Operated Valve	470.4	Gulf Coast Segment
290-LIBRT-05A-B0-MLV-01	Motor Operated Valve	478.1	Gulf Coast Segment

^aThe Houston Lateral will have 8 valves that meet the 20-mile spacing requirement stipulated in Special Condition 32 and all the other design criteria (4 motor-operated valves upstream of Trinity and Sabine Rivers; 2 manually operated valves and 2 check valves downstream of Trinity and Sabine Rivers). As of this writing, exact milepost locations are being updated.

These proposed valve locations have been reviewed during the environmental analysis. Given public and agency concerns over sensitive environmental resources, DOS in consultation with PHMSA and EPA determined that Keystone should commission an engineering analysis by an independent consultant that would review the proposed Project risk assessment and proposed valve placement. The engineering analysis would, at a minimum, assess the advisability of additional valves and/or the deployment of external leak detection systems in areas of particularly sensitive environmental resources. The scope of the analysis and the selection of the independent consultant would be approved by DOS with concurrence from PHMSA and EPA. After completion and review of the engineering analysis, DOS with concurrence from PHMSA and EPA would determine the need for any additional mitigation measures.

2.2.3 Piggings Facilities

Keystone would use high-resolution internal line inspection, maintenance, and cleaning tools known as “pigs” during operation of the proposed Project. The proposed Project would be designed to allow full pigging of the entire pipeline, with minimal interruption of service. Pig launchers and receivers would be constructed and operated completely within the boundaries of the pump stations (see Figures 2.2.3-1 and 2.2.3-2) or delivery facilities.

2.2.4 Densitometer Facilities

Densitometer facilities on the pipeline would be equipped with densitometer/viscometer analyzers which measure the density of the product prior to delivery. Densitometer information would be incorporated into quality and custody metering located at all injection points and at all delivery points.

Keystone proposes to install and operate four densitometers within the permanent ROW. One of the densitometers would be on the Steele City Segment, two would be on the Gulf Coast Segment, and one would be on the Houston Lateral. The locations of the densitometers are listed below:

- Upstream side of Pump Station 26 (Saline County, Nebraska; MP SCS-820.8);
- Upstream side of Pump Station 41 (Liberty County, Texas; MP GCS-429.9);
- Upstream side of the Nederland delivery station (Jefferson County Texas; MP GCS-477.8); and
- Upstream side of the delivery station near Moore Junction (Harris County Texas; MP HL-42.6).

2.2.5 Delivery Sites

Keystone would install two crude oil delivery facilities in Texas. One would be at the end of the Gulf Coast Segment in Nederland within a terminal owned and operated by Sunoco Logistics. The second would be installed at the end of the Houston Lateral at Moore Junction on a previously disturbed site. Each delivery facility would have a pig receiver on the incoming pipeline and would connect to a surge relief system and a metering system installed upstream of a manifold owned by the third party receiving crude oil transported by the proposed Project. The surge relief system at the Nederland delivery site would include two surge relief tanks, each with a capacity of approximately 10,417 barrels (435,514 gallons) (see Section 2.1.1.3). The delivery facilities would also include pressure regulating equipment, flow control valves, isolation valves, and a quality measurement building that would include a densitometer and a sampling system. Each delivery facility would also include a sump tank with injection pumps to receive oil from the drains of safety valves and traps. The drain system piping would connect to the main line to return captured oil to the pipeline.

The delivery facilities would operate on locally provided power.

2.2.6 Cushing Tank Farm

Keystone originally proposed to construct a tank farm in Steele City, Nebraska to manage the movement of oil through the system. However, after completing a detailed operational review of the proposed Project, Keystone determined that there would be greater operational efficiency if the tank farm were installed near Cushing, adjacent to the existing Cushing Oil Terminal, which is the largest crude oil storage facility in the U.S. and has a substantial network of connecting crude oil pipelines.

Keystone proposes to construct a tank farm on an approximately 74-acre site that is approximately 2,000 feet from the southern end of the existing Cushing Oil Terminal. The site would also include Pump Station 32. The plot plan for the Cushing tank farm is presented on Figure 2.2.6-1. As indicated on that figure, there is sufficient room on the site to house the facilities proposed for the Bakken and Cushing Marketlink projects, which are two connected actions described in Sections 2.5.3 and 2.5.4.

The Cushing tank farm would include three, 350,000-barrel aboveground storage tanks. Each tank would have a single-deck pontoon external floating roof with provisions for installation of geodesic fixed roofs. The tanks would be installed inside an impervious bermed area that would act as secondary containment. The piping in the tank farm site would be both above and below ground. The tank farm would also

include four booster pumps, two sump tanks, two positive displacement meters, pig launchers and receivers, two electrical buildings, a field service building, and parking for maintenance personnel. The tanks and associated piping would be isolated electrically from the pipeline and protected by a separate cathodic protection system. The tank farm would operate on locally purchased electricity and would be fully automated for unmanned operation.

Down-lighting would be used to light the tank farm wherever possible to minimize impacts to wildlife. A security fence would be installed around the entire tank farm. Inspection and maintenance personnel would access the tank farm through a gate that would be locked when no one is at the tank farm.

In addition to the design requirements for the pipe for the proposed Project, procedures, specifications, applicable codes and standards promulgated by the organizations listed below would be used for the design of the Cushing tank farm facility:

- Oklahoma Corporation commission – adopts DOT part 195 as outlined in Oklahoma Administrative Code 165 Chapter 20, Gas and Hazardous Liquid Pipeline
- American Petroleum Institute – API
- American Society of Testing and Materials – ASTM
- American Welding Society – AWS
- Institute of Electrical and Electronics Engineers – IEEE
- Instrument Society of America – ISA
- International Organization for Standardization – ISO
- Manufacturers Standardization Society of the Valve and fittings industry – MSS
- National Electrical Safety Code – NEC
- National Electrical Manufacturers Association – NEMA
- National Fire Protection Association – NFPA
- Occupational Safety and Health Administration – OSHA
- Pipeline and Hazardous Material Safety Administration – PHMSA
- Steel Structure Painting Council – SSPC
- Underwriters Laboratories – UL

2.2.7 Ancillary Facilities

2.2.7.1 Additional Temporary Workspace Areas

Additional temporary workspace areas would be needed for some construction staging areas and where special construction techniques are to be used. These areas would include river, wetland, and road/rail crossings; horizontal directional drilling (HDD) entry and exit points; steep slopes (20 to 60 percent); and rocky soils. The setback distances of temporary workspace areas adjacent to wetland and waterbody features would be established on a site-specific basis, consistent with applicable permit requirements and the appropriate procedures listed in the CMR Plan (Appendix B). The location of additional temporary workspace areas would be adjusted as design of the proposed Project is refined.

The dimensions and acreages of typical additional temporary workspace areas are listed in Table 2.2.7-1.

Crossing Type	Dimensions (length by width in feet at each side of feature crossed)	Acreage
Waterbodies crossed using HDD	250 x 150, as well as the length of the drill plus 150 x 150 on exit side	1.4
Waterbodies ≥ 50 feet wide	300 x 100	0.7
Waterbodies < 50 feet wide	150 x 25 on working and spoil sides or 150 x 50 on working side only	0.2
Bored highways and railroads	175 x 25 on working and spoil sides or 175 x 50 on working side only	0.2
Open-cut or bored county or private roads	125 x 25 on working and spoil sides or 125 x 50 on working side only	0.1
Foreign pipeline/utility/other buried feature crossings	125 x 50	0.1
Push-pull wetland crossings	50 feet x length of wetland	Varies
Construction spread mobilization and demobilization	470 x 470	5.1
Stringing truck turnaround areas	200 x 80	0.4

2.2.7.2 Pipe Storage Sites, Railroad Sidings, and Contractor Yards

Construction would require establishment and use of pipe storage sites, railroad sidings, and contractor yards. Pipe storage sites would be required at 30- to 80-mile intervals and contractor yards would be required at approximately 60-mile intervals. Keystone estimated that 40 pipe storage yards and 19 contractor yards would be required for the proposed Project. Table 2.2.7-2 provides the locations and acreages of potential pipe storage yards and contractor yards.

State	Types and Numbers of Yards	Counties	Combined Acreage
Montana	Contractor Yards (3)	Valley, McCone, Dawson	90.6
	Railroad Siding (5)	Valley, Fallon, Roosevelt, Dawson (2)	100.0
	Pipe Stockpile Sites (9)	Phillips, Valley (2), McCone (2), Dawson (2), Fallon (2)	270.1
South Dakota	Contractor Yards (5)	Harding, Meade, Haakon, Jones, Tripp	150.2
	Railroad Siding (5)	Butte, Pennington (2), Stanley, Hutchinson	100.0
	Pipe Stockpile Sites (11)	Harding (3), Meade (2), Haakon (2), Jones (2), Tripp (2)	331.0
Nebraska	Contractor Yards (7)	Holt (2), Greeley, Merrick, York, Gage, Jefferson	213.3
	Railroad Siding (3)	Merrick, York, Jefferson	60.0
	Pipe Stockpile Sites (8)	Keya Paha, Holt (2), Greeley, Nance, Hamilton, Fillmore, Jefferson	242.3
Kansas	Contractor Yards	None	0
	Pipe Stockpile Sites	None	0

TABLE 2.2.7-2 Locations and Acreages of Proposed Pipe Storage Sites, Railroad Sidings, and Contractor Yards			
State	Types and Numbers of Yards	Counties	Combined Acreage
Oklahoma	Contractor Yards (3)	Hughes, Lincoln, Bryan	65.2
	Railroad Siding (1)	Pittsburg	9.2
	Pipe Stockpile Sites (3)	Bryan, Lincoln, Hughes	258.1
	Pipe Stockpile Sites/Railroad Siding (4)	Pottawatomie, Grady (2), Hughes	378.0
Texas	Contractor Yards (8)	Angelina, Nacogdoches, Cherokee, Liberty, Houston, Lamar, Titus, Rusk	141.4
	Railroad Siding (5)	Titus, Angelina, Franklin, Hardin, Lamar	27.6
	Pipe Stockpile Sites (5)	Orange, Jefferson, Polk (2), Lamar	237.5
	Pipe Stockpile Sites/Railroad Siding (2)	Grayson/Fannin, Franklin/Titus	91.1
	Pipe Stockpile Sites/Contractor Yards (2)	Angelina, Lamar	21.9

Each pipe storage site would occupy approximately 30 to 40 acres and would typically be located close to railroad sidings. Contractor yards would occupy approximately 30 acres. Keystone would select existing commercial/industrial sites or sites that were used for construction of other projects as preferred sites for the storage sites.

Existing public or private roads would be used to access the yards. Pipe storage sites and contractor yards would be used on a temporary basis and would be reclaimed, as appropriate, upon completion of construction.

2.2.7.3 Fuel Transfer Stations

Fuel storage sites would be established at approved contractor yards and pipe storage sites. No other fuel stations would be constructed. Fuel would be transported daily by fuel trucks from the yards to the construction area for equipment fueling.

Each fuel storage system would consist of the following:

- Temporary, aboveground 10,000- to 20,000-gallon skid-mounted tanks and/or 9,500-gallon fuel trailers;
- Rigid steel piping;
- Valves and fittings;
- Dispensing pumps; and
- Secondary containment structures.

The fuel storage system would have a secondary containment structure capable of holding 110 percent of the volume of the fuel storage tanks or fuel trailers. Containment structures would consist of sandbags or earthen berms with a chemically resistant membrane liner. Typical diesel and gasoline fuel storage systems are depicted on Figures 2.2.7-1 and 2.2.7-2.

The total fuel storage capacity would vary from yard to yard, depending on daily fuel requirements. Typically, a 2- to 3-day supply of fuel would be maintained in storage, resulting in a maximum volume of approximately 30,000 gallons of fuel at each storage location.

Prior to the receiving or off-loading of fuel, the trucks and equipment would be grounded to eliminate static electricity potential. The distributor would connect a petroleum-rated hose from the delivery tanker to the fill line at the storage facility. The fill truck connection and fill line would consist of a cam-loc connection followed by a block valve, rigid steel piping, tank block valve(s), and check valve(s) just upstream of the connection to the tank. Off-loading of fuel would be accomplished by a transfer pump powered by the delivery vehicles. For dispensing gasoline and on-road diesel fuel, the transfer pump would be a dispensing pump with petroleum-rated hoses with automatic shut-off nozzles. The fuel transfer pump would have an emergency shut-off at the pump and a secondary emergency shut-off at least 100 feet away.

Vehicle maintenance would be performed at the contractor yards or at existing vehicle maintenance and repair shops.

2.2.7.4 Construction Camps

Some areas within Montana and South Dakota do not have sufficient temporary housing in the vicinity of the proposed route to house all construction personnel working on spreads in those areas. In those remote areas, temporary work camps would be constructed to meet the housing needs of the construction workforce. A total of four temporary construction camps would be established: two would be in Montana, near Nashua and Baker, and two would be in South Dakota, near Union Center and Winner (see Figure 2.2.7-3). Depending on the final construction spread configuration and construction schedule, additional or larger camps may be required. The number and size of camps would be determined based on the time available to complete construction and to meet Keystone’s commercial commitments. All construction camps would be permitted, constructed, and operated consistent with applicable county, state, and federal regulations. The relevant regulations that would have to be complied with and the permits required for the construction camps are presented in Table 2.2.7-3.

TABLE 2.2.7-3 Construction Camp Permits and Regulations	
Agency / State	Permit / Discussion
Montana	
Montana Department of Environmental Quality (MDEQ)	<p>Public water and sewer (PWS) laws, Title 75, chapter 6, part 1, Montana Code Annotated (MCA). Rules at Administrative Rules of Montana (ARM) 17.38 101, and Department Circulars incorporated by reference. Require plan and specification review before construction of a public water or sewer system. Circulars contain design requirements. Requires water quality monitoring of water supply.</p> <p>Sanitation in subdivisions laws, Title 76, Chapter 4, MCA. Rules at ARM Title 17, Chapter 36. If applicable (e.g., if the site is less than 20 acres), requirements the same as PWS laws and Circulars for water supply and wastewater. Would require additional review of stormwater systems and solid waste management. (Likely not applicable unless “permanent” multiple spaces created for mobile homes or RVs. 76-4-102(16), MCA.)</p> <p>Water Quality Act Discharge Permits, Title 75, Chapter 5, MCA. Rules at ARM Title 17, Chapter 30. Groundwater discharge permit would be required if a wastewater drain field had a design capacity over 5,000 gallons per day (gpd). ARM 17.30.1022.</p> <p>Air Quality Permits, Title 17, Chapter 8, Subchapter 7. Permits would be</p>

**TABLE 2.2.7-3
Construction Camp Permits and Regulations**

Agency / State	Permit / Discussion
Department of Public Health and Human Services (DPHHS)	<p>required for sources with potential emissions exceeding 25 tons per year (tpy) unless exemptions exist and are met for temporary non-road engines.</p> <p>Work Camp licensing laws, Title 50, Chapter 52, MCA. Rules at ARM Title 37, Chapter 111, Subchapter 6. Regulations regarding water, sewer, solid waste, and food service. Incorporates MDEQ PWS requirements but has additional water and sewer provisions. Administered by DPHHS, Public Health and Safety Division, Communicable Disease Control and Prevention Bureau, Food and Consumer Safety Section.</p>
Counties	<p>Permit required for wastewater systems, regulations adopted under Section 50-2-116(1)(k), MCA. Adopting state minimum standards promulgated by Board of Environmental Review at ARM Title 17, Chapter 36, Subchapter 9. Generally follow state laws for subdivisions, PWS, DEQ-4.</p> <p>Work camp permit required in some counties.</p>
South Dakota	
South Dakota Department of Environment and Natural Resources Drinking Water Program and Surface Water Quality Program	<p>Permit required for a Transient Non-community (TNC) PWS. There also are sampling requirements for a TNC PWS.</p> <p>A National Pollution Discharge Elimination System Permit would be required for waste water discharge.</p>
South Dakota Administrative Rules	<p>Air Quality Permit, Chapters 74:36:04-05. The diesel-fired generator engines and emergency back-up generators at each camp in South Dakota would require a minor operating permit, unless exemptions exist and are met for temporary nonroad engines.</p>
Counties	<p>An approach permit and a building permit may be necessary in some counties.</p> <p>A wide load permit is necessary for transport of modulars units to camps.</p>

Design of Camps

Each construction camp site would be established on an approximately 80-acre site. Of that area, 30 acres would be used as a contractor yard, and 50 acres would be used for housing and administration facilities. The camps would be constructed using modular units and would provide the required infrastructure and systems necessary for complete food service, housing, and personal needs, including a convenience store, recreational and fitness facilities, entertainment rooms and facilities, telecommunications/media rooms, kitchen/dining facilities, laundry facilities, and security units. Each camp would also have a medical infirmary for first aid needs and to provide routine minor medical services for the workers and staff.

There would also be dedicated medical transport vehicles for both the camp sites and for the construction ROW.

Housing facilities of the camps would consist of modular, dormitory-like units that house roughly 28 occupants per unit. The units would have heating and air conditioning systems. The camps would be set up with the housing areas clustered together, with both shared and private wash rooms. Each camp site would provide parking for about 100 recreational vehicles. Each camp would accommodate approximately 600 people.

Potable water would be provided by drilling a well where feasible. If an adequate supply cannot be obtained from a well, water would be obtained from municipal sources or trucked to each camp. A self-contained wastewater treatment facility would be included in each camp except where it is practicable to use a licensed and permitted publically owned treatment works (POTW). Wastewater treated on site would undergo primary, secondary, and tertiary treatment consisting of solids removal, bioreactor treatment, membrane filtration, and ultraviolet exposure. Final effluent discharge would be consistent with all applicable regulatory requirements. If a POTW is used, Keystone would either pipe or truck wastewater to the treatment facility.

Electricity for the camps would either be generated on site through diesel-fired generators, or would be provided by local utilities from an interconnection to their distribution system. Keystone would contract with a camp supplier that would provide security 24 hours per day, 7 days per week at each camp. Keystone would work with the supplier to ensure that as many local employees are hired as possible to staff the camps.

Use of Camps

The camps are planned to service the needs of the proposed Project work force. As a result, the dormitories do not include facilities for families. However, workers using the recreational vehicle areas may include family members.

Most of the workers would be transported to and from the ROW each day by buses. In addition, there would be individual crews and workers that, due to the nature of their work, would be transported to and from job sites by utility trucks or by welding rigs. There would also be support workers such as mechanics, parts and supply staff, and supervisory personnel that would drive to the ROW in separate vehicles.

Based on the current construction schedule, the camps would operate in standby mode during the winter (from December through March or April). Each camp would have sufficient staff to operate and secure the camp plant and systems during that time period.

Decommissioning of Camps

Decommissioning would be accomplished in two stages. First, all infrastructure systems would be removed and either hauled away for re-use, recycled, or disposed of in accordance with regulatory requirements. Each site would then be restored and reclaimed in accordance with permit requirements and the applicable procedures described in Keystone's CMR Plan (Appendix B).

2.2.7.5 Access Roads

Development of Access Roads

Existing public and private roads would be used to provide access to most of the construction ROW. Paved roads would not likely require improvement or maintenance prior to or during construction. However, the road infrastructure would be inspected prior to construction to ensure that the roads, bridges and cattle guards would be able to withstand oversized vehicle use during construction. Gravel roads and dirt roads may require maintenance during the construction period due to high use. Road improvements such as blading and filling would generally be restricted to the existing road footprint; however, some roads may require widening in some areas.

To the extent Keystone is required to conduct maintenance of any county roads, it would be done pursuant to an agreement with the applicable county. In the event that oversized or overweight loads would be needed to transport construction materials to the proposed Project work sites, Keystone would submit required permit applications to the appropriate state regulatory agencies.

Approximately 400 temporary access roads would be needed to provide adequate access to the construction sites. Private roads and any new temporary access roads would be used and maintained only with permission of the landowner or the appropriate land management agency. Keystone would also construct short permanent access roads from public roads to the tank farm, pump stations, delivery facilities, and intermediate MLVs. Approximately 50 permanent access roads would be needed.

The final locations of new permanent access roads would be determined prior to construction. At a minimum, construction of new permanent access roads would require completion of cultural resources and biological surveys and consultations and approvals of the appropriate SHPO and USFWS office. Other state and local permits also could also be required prior to construction. Maintenance of newly created access roads would be the responsibility of Keystone as described below.

The acreages of access roads are included in the listing of lands affected in Table 2.1.4-1. Access road temporary and permanent disturbance estimates are based on the 30-foot roadway width required to accommodate oversized vehicles. In developing the acreages of disturbance, all non-public roads were conservatively estimated to require upgrades and maintenance during construction.

Roadway Maintenance, Repair, and Safety

There were many comments on the draft EIS concerning the maintenance and repair of road surfaces used during construction and operation of the proposed Project, as well as comments expressing concern about roadway safety. If the proposed Project receives all permits and approvals, Keystone would work with state and local road officials, the pipeline construction contractor, and a third-party road consultant to identify routes that would be used for moving materials and equipment between storage and work yards to the pipeline, valve, and pump station construction sites. When these routes are mutually agreed upon, the road consultant would document the existing conditions of roads, including a video record. When construction is completed, the same parties would review the road conditions, and Keystone would restore the roads to their preconstruction condition or better. This restoration would be paid for by Keystone.

Keystone would also perform a preliminary evaluation to determine the design-rated capacity of bridges anticipated to be used during construction and would inspect all bridges it intends to use prior to construction and confirm that the capacity of the bridges is adequate for the anticipated weights. In cases where the bridges are not adequate to handle the maximum weight, an alternate route would be used. Keystone would also inspect cattle guard crossings prior to their use. If they are determined to be inadequate to handle anticipated construction traffic, Keystone may place mats on crossings, establish an alternate crossing, enhance existing structures, or install new infrastructure with the landowner's approval. All such actions would be paid for by Keystone.

During construction, Keystone and the pipeline contractor would maintain roads used for construction in a condition that is safe for both the public and work force. Local road officials would be actively engaged in the routine assessment of road conditions.

Keystone would follow all federal, state, and local safety plans and signage as set forth in current Manuals of Uniform Traffic Control for streets and highways, or in similar documents issued by regulatory agencies along the proposed route. This would include compliance with all state and local permits pertaining to road and crossing infrastructure usage.

Keystone would require that each construction contractor submit a road use plan prior to mobilization, coordinate with the appropriate state and county representatives to develop a mutually acceptable plan, and obtain all necessary road use permits. The road use plans would identify potential scenarios that may occur during construction based on surrounding land use, known recreational activities, and seasonal influences (such as farming), and would establish measures to reduce or avoid effects to local communities. Keystone would also have inspection personnel monitor road use activities to ensure that the construction contractors comply with the road use plans and stipulations of the road.

Commenters also expressed concern that some counties in Montana stipulate that a private individual conducting maintenance of a county road becomes liable for the safety of traffic on the road. Keystone has stated that to the extent it is required to conduct maintenance of any county road in Montana, it would be done pursuant to an agreement with the applicable county, and such agreement would address potential liability, including appropriate indemnity and insurance provisions. Further, Keystone has the necessary insurance coverage to address such potential liability.

2.3 PIPELINE SYSTEM DESIGN AND CONSTRUCTION PROCEDURES

Many commenters expressed concerns about the safety of the proposed Project, the use of industry standards in the design of the proposed Project, and the inspection and monitoring procedures that would be conducted. The USDOT's Pipeline and Hazardous Materials Administration (PHMSA) is responsible for protecting the American public and the environment by ensuring the safe and secure movement of hazardous materials to industry and consumers by all transportation modes, including the nation's pipelines. Through PHMSA, the USDOT develops and enforces regulations for the safe, reliable, and environmentally sound operation of the nation's 2.3-million-mile pipeline transportation system and the nearly 1 million daily shipments of hazardous materials by land, sea, and air. Within PHMSA, the Office of Pipeline Safety (OPS) has the safety authority for the nation's natural gas and hazardous liquid pipelines. The proposed Project is included in the latter category.

As described below, to protect the public and environmental resources, Keystone would be required to construct, operate, maintain, inspect, and monitor the Project consistent with the PHMSA requirements presented in 49 CFR 195 (Transportation of Hazardous Liquids by Pipeline), as well as relevant industry standards, and applicable state standards. These regulations specify pipeline material and qualification standards, minimum design requirements, and required measures to protect the pipeline from internal, external, and atmospheric corrosion. The regulations are designed to prevent crude oil pipeline accidents and to ensure adequate protection for the public.

In addition, Keystone would comply with a set of 57 Special Conditions developed by PHMSA for the proposed Project (see Appendix U). Originally, PHMSA began development of these conditions in consideration of a special permit request from Keystone that, if granted, would have allowed Keystone to operate the Project at a maximum operating pressure higher than would be allowed using the specified design factor in 49 CFR 195.106. On August 5, 2010, Keystone withdrew its application to PHMSA for a special permit. However, DOS continued to work with PHMSA to develop Special Conditions in response to comments received about pipeline construction, operation, and maintenance. Keystone agreed to incorporate the Special Conditions into the proposed Project and would include those conditions in its manual for operations, maintenance, and emergencies that is required by 49 CFR 195.402. PHMSA has the legal authority to inspect and enforce any items contained in a pipeline operator's operations, maintenance, and emergencies manual, and would therefore have the legal authority to inspect and enforce the 57 Special Conditions if the proposed Project is approved. DOS, in consultation with PHMSA, has determined that incorporation of those conditions would result in a Project that would have a degree of safety over any other typically constructed domestic oil pipeline system under current

code and a degree of safety along the entire length of the pipeline system similar to that which is required in High Consequence Areas (HCAs) as defined in 49 CFR 195.450.

Several commenters have recommended that the pipeline be constructed above ground. While it would be technically feasible to construct the pipeline aboveground in most areas along the proposed route, there are many disadvantages to an aboveground pipeline. In comparison to an aboveground pipeline, burying a pipeline reduces the potential for pipeline damage due to vandalism, sabotage, and the effects of other outside forces, such as vehicle collisions. Further, there has been increased concern about homeland security since the September 11, 2001 attacks, and burying the pipeline provides a higher level of security. Further, an above ground pipeline would be more susceptible to the effects of ambient temperature, wind, and other storm events. Construction of an aboveground pipeline would also require exposing the pipeline above rivers (e.g., hung from a bridge or constructed as a special pipeline span) and roadways where it would be more accessible to those intent on damaging the pipeline.

Nearly all petroleum pipelines in the U.S. are buried, and Keystone has also proposed to bury the proposed Project pipeline. As described above, the facilities would be designed, constructed, tested, and operated in accordance with the regulations in 49 CFR 195, the 57 Special Conditions provided to Keystone by PHMSA, and all other applicable federal and state regulations.

If the proposed Project is approved and implemented, PHMSA would maintain continual regulatory oversight over the Project, throughout construction, testing, start-up, operation, and maintenance. The PHMSA regulations presented in 49 CFR 195 Transportation of Hazardous Liquids by Pipeline specify pipeline material and qualification standards, minimum design requirements, and required measures to protect the pipeline from internal, external, and atmospheric corrosion. The regulations are designed to prevent crude oil pipeline accidents and to ensure adequate protection for the public. Section 2.3.1 presents the major pipeline design considerations of the proposed Project. In addition, the Special Conditions provide more stringent requirements for many of these design factors.

Keystone prepared a draft CMR Plan that was included in Appendix B of the draft EIS. That plan described the construction methods and environmental protection measures that Keystone committed to in order to reduce the potential construction impacts of the proposed Project. The CMR Plan was revised after the publication of the draft EIS to update the procedures based on agency reviews and input. The current version of the plan is presented in Appendix B. If the proposed Project is issued a Presidential Permit, the CMR Plan would be updated after the ROD is issued to reflect any additional conditions included in the ROD and in other permits issued to Keystone, and to reflect regional construction considerations.

Prior to pipeline construction, Keystone would prepare a Spill Prevention, Control, and Countermeasure (SPCC) Plan to avoid or minimize the potential for harmful spills and leaks during construction. A draft version of the SPCC submitted by Keystone is included in Appendix C.

EPA submitted a comment expressing concern that the non-transportation related equipment and activities at pump stations, breakout tanks, and the tank farm may require the submission and some cases, approval, of a Facility Response Plan (FRP) as required under 40 CFR 112.20. However, it appears unlikely that the proposed Project would be required to submit an FRP under 40 CFR 112.20 for equipment and activities at the pump stations, the Cushing tank farm, or the surge relief tanks at the Nederland delivery point. Those facilities would not house any non-transportation-related equipment or activities subject to the requirement to prepare and submit an FRP. Further, 40 CFR 112.20 requires an FRP if a facility could reasonably be expected to cause substantive harm to the environment by discharging oil into or on the navigable waters or adjoining shorelines. However, if EPA makes the determination that any or all of

those facilities meet the criteria for an FRP within 40 CFR 112.20, Keystone would be required to prepare and submit an FRP to EPA for review.

In addition, Keystone would submit a Pipeline Spill Response Plan (PSRP) to PHMSA prior to the initiation of proposed Project operations in accordance with the requirements of 49 CFR 194. The PSRP would describe how spills would be responded to in the event of a release from the proposed Project resulting from any cause as well as the maximum spill scenario and the procedures that would be in place to deal with the maximum spill. As required by 49 CFR 195.40, Keystone would also prepare and follow a manual of written procedures for conducting normal operations and maintenance activities and handling abnormal operations and emergencies that would include Keystone’s Emergency Response Plan (ERP). The PSRP and the ERP are addressed in Sections 2.4.2.2 and 3.13.5.5.

The remainder of this section provides information on the following topics:

- Pipeline Design (Section 2.3.1);
- Pipeline Construction Procedures (Section 2.3.2);
- Special Pipeline Construction Procedures (Section 2.3.3);
- Construction Procedures for Aboveground and Ancillary Facilities (Section 2.3.4);
- Construction Schedule and Workforce (Section 2.3.5); and
- Construction Conditions Imposed by PHMSA (Section 2.3.6).

2.3.1 Pipeline Design

2.3.1.1 Pipe Specifications

All pipe used for the proposed Project would be required to be in compliance with the pipe design requirements of 49 CFR 195, Subpart C (Design Requirements) and PHMSA Special Conditions 1, 2, 3, 4, 7, and 8. The pipeline would be constructed of high-strength X70 steel pipe that would be mill-inspected by an authorized owner’s inspector and mill-tested to API 5L (American Petroleum Institute [API] 5L³) specification requirements. Key design parameters applicable to the proposed Project pipeline are listed in Table 2.3.1-1.

TABLE 2.3.1-1 Pipe Design Parameters and Specification	
Pipe Design Parameters	Specification
Material code	API 5L-PSL2-44 th Edition
Material grade thousand pounds of pressure per square inch (ksi) (yield strength) ^a	Grade X70
Maximum pump station discharge	1,308 pounds per square inch gauge (psig)
Maximum Operating Pressure (MOP)	1,308psig; 1,600 psig ^a

³ The American Petroleum Institute (API) 5L test standard is used to determine the fracture ductility of metal line pipe. Specimens are cut from sections of pipe, soaked at a prescribed temperature, and tested within 10 seconds.

**TABLE 2.3.1-1
Pipe Design Parameters and Specification**

Pipe Design Parameters	Specification
Minimum hydrostatic test pressure	In conformance with Special Conditions 8 and 22, the pipe must be subjected to a mill hydrostatic test pressure of 95% SMYS or greater for 10 seconds and the pre-in service hydrostatic test must be to a pressure producing a hoop stress of a minimum 100% SMYS for mainline pipe and 1.39 times MOP for pump stations for eight (8) continuous hours. The hydrostatic test results from each test must be submitted in electronic format to the applicable PHMSA Director(s) in PHMSA Central, Western and Southwest Regions after completion of each pipeline.
Joint length (feet)	Nominal 80-foot (double-joint)
Field production welding processes	Mechanized – gas metal; arc welding (GMAW); Manual-shielded metal arc welding (SMAW)
Pipeline design code	49 CFR Part 195
Outside diameter	36 inches
Line pipe wall thickness (0.72 design factor as per 49 CFR 195.106)	0.465 inch
Heavy wall thickness – High Consequence Areas (HCAs) including, high population areas, other populated areas, unusually sensitive areas, including drinking water and ecologically sensitive areas, mainline valve and pump station sites.	0.515 inch
Heavy wall thickness – directly downstream of pump stations at lower elevations as determined by steady state and transient hydraulic analysis. ^a	0.572 inch
Heavy wall thickness – uncased road and cased railway crossings	0.618 inch
Heavy wall thickness – uncased railway crossings, horizontal directional drillings (HDDs) ^a	0.748 inch

^a The design of the proposed Project pipeline system is based on a maximum 1,308 pounds per square inch gauge (psig) discharge pressure at each pump station. The pump station discharge pressure would be a maximum of 1,308 psig. There would be situations where, due to elevation changes, the hydraulic head created would result in a Maximum Operating Pressure of up to and including 1,600 psig. Suction pressure at the pump stations is generally on the order of 200 psig.

Commenters have expressed concern about the quality of pipe used for the proposed Project and the countries of origin of the pipe. Keystone has stated that approximately 75 percent of the pipe for the U.S. portion of the proposed Project would be purchased from North American pipe manufacturing facilities and that regardless of the country of origin, it would purchase pipe only from qualified pipe suppliers and trading houses. Qualification includes comprehensive evaluations of manufacturing facilities, extensive technical discussions with the lead quality control and metallurgy personnel, and a clear demonstration that the mills can meet the requirements to produce and test pipe in accordance with Keystone’s standards and specifications.⁴ In addition, as noted above, all pipe used for the proposed Project would have to be manufactured and tested in accordance with the requirements of 49 CFR 195 and the 57 Project-specific Special Conditions developed in consultation with PHMSA and accepted by Keystone.

⁴ Keystone would use TransCanada Pipelines pipe specifications for the proposed Project where those specifications exceed federal regulations and the PHMSA Special Conditions.

Keystone would review, and if appropriate, approve the pipe manufacturer's procedure specifications prior to the pipe mill initiating purchase or production of steel to ensure the material meets the API 5L Line Pipe Specification and Keystone's Corporate Specifications and Project-specific requirements. Surveillance personnel would be stationed in the pipe mill through the duration of production to inspect the finished pipe and monitor compliance to the specifications throughout the manufacturing process. These personnel would monitor things such as mill test reports and other appropriate documentation, including production logs, steel quality, fabrication, welding rejection summaries, lab results, and non-conformance reports.

TransCanada's pipe manufacturing specifications also specify that any deviation in the rolling process requires testing to be recommenced from the point of deviation to ensure uniformity. Finally, additional mechanical and chemical property tests based on steel grade, plate, and/or coil would be completed based on the steel manufacturing process as well as rolling and cooling temperatures. Those tests ensure that steel properties are not variable.

2.3.1.2 External Corrosion Protection

To protect against corrosion, an external coating (fusion-bonded epoxy, or FBE) would be applied to the pipeline and all buried facilities, and cathodic protection (CP) would be applied to the pipeline by impressed current. These measures would be provided in compliance with 49 CFR Part 195, Subpart H (Corrosion Control) and the requirements of 14 of the PHMSA 57 Special Conditions (see Appendix U). The primary impressed current CP systems would be rectifiers coupled to semi-deep vertical anode beds at each pump station, as well as rectifiers coupled to deep-well anode beds at selected intermediate mainline valve sites. The rectifiers would be variable output transformers which would convert incoming AC power to DC voltage and current to provide the necessary current density to the CP design structures. The rectifiers would have a negative cable connection to the design structure and a positive cable connection to the anode beds. The anode beds would consist of high silicon cast iron anodes backfilled with a highly conductive coke powder to allow for an expected anode minimum life of 20 years. During operation, the CP system would be monitored and remediation performed to prolong the anode bed and systems. The semi-deep anode beds would be 12-inch-diameter vertical holes spaced 15 feet apart with a bottom hole depth of approximately 45 feet. The deep-well anode bed would be a single 12-inch-diameter vertical hole with a bottom hole depth of approximately 300 feet.

2.3.2 Pipeline Construction Procedures

Once engineering surveys of the ROW centerline and additional temporary workspace areas have been finalized, and the acquisition of ROW easements and any necessary acquisitions of property in fee have been completed, construction would begin. Several commenters have expressed concern about the negotiation process for easement agreements along the proposed route and the use of eminent domain for the procurement of some easements. Commenters have also suggested that the applicant is a Canadian company and should not be allowed to use the eminent domain process to obtain easements. In addition, some commenters have expressed concern about their options if Keystone does not comply with easement agreements.

Keystone is a U.S. corporation that was incorporated in accordance with the laws of the State of Delaware. Keystone is the corporate entity that will construct the pipeline if it is approved. Keystone is therefore eligible to use eminent domain laws. To construct, operate, and maintain the proposed Project, Keystone would need the rights to easements along the entire proposed route. Keystone is responsible for negotiating easement agreements with landowners along the route in each state. The easement agreements would list the conditions that both the landowner and Keystone agree to, including financial compensation to the landowners in return for granting easements. Compensation would also be made for

loss of use during construction, crop loss, loss of non-renewable or other resources, and restoration of any unavoidable damage to personal property during construction. DOS expects Keystone to negotiate fairly, honestly, and respectfully with landowners when they negotiate an easement. However, those negotiations and final agreements are private business concerns between the landowners and Keystone, and DOS has no legal authority or ability to intervene in the proceedings.

If Keystone obtains all necessary permits and approvals and an easement negotiation cannot be completed in a manner suitable to both parties, Keystone would use state eminent domain laws to obtain easements needed for pipeline construction, maintenance, and operation. State laws dictate under what circumstances eminent domain may be used and define the eminent domain process within the state. The level of compensation would be determined by a court according to applicable state law. Again, DOS has no legal authority or ability to intervene in eminent domain proceedings. In addition, eminent domain does not apply to land under federal ownership or management.

State or local trespass and access laws are applicable along the entire route and therefore along each easement negotiated by Keystone and the landowner or obtained by Keystone through the eminent domain process. As noted above, DOS has no legal authority over negotiating easement agreements and has no legal status to enforce the conditions of an easement agreement. A landowner who considers Keystone to be out of compliance with an easement agreement would have take up the matter with Keystone or local law enforcement officials, or initiate legal consultation.

As proposed, the pipeline would be constructed in 17 spreads. Final spread configurations and the final construction schedule may result in the use of additional spreads or fewer shorter or longer spreads. Figure 2.3.2-1 depicts the approximate location of each spread. The 851.6-mile-long Steele City Segment would be constructed using 10 mainline spreads from approximately 63 to 109 miles long. Construction of the 483.8-mile-long Gulf Coast Segment pipeline would be accomplished using 6 spreads from about 49 to 100 miles in length. The 48.6-mile-long Houston Lateral would be constructed using one spread.

Pipeline construction would generally proceed as a moving assembly line composed of specific activities including surveying and staking of the ROW, clearing and grading, pipe stringing, bending, trenching, welding, installing, backfilling, hydrostatic testing, and cleanup, as described in the subsections below and illustrated in Figure 2.3.2-2. In addition, special construction techniques would be used for specific site conditions such as rugged terrain, waterbodies, wetlands, paved roads, highways, and railroads. These non-standard pipeline construction procedures are described in Section 2.3.3.

On the Steele City Segment, construction is planned to continue into the early winter months for as long as the weather permits construction without the use of special winter construction techniques. However, as stated in the CMR Plan (Appendix B), if the proposed Project is authorized and winter construction is necessary to meet construction deadlines, Keystone would consult with the relevant federal, state, and local regulatory agencies to determine what changes may be necessary in permits issued, what additional permits may be required, and to identify the procedures that would have to be incorporated into construction to avoid or minimize environmental impacts. Winter construction plans would be finalized based on those consultations and permit requirements. On the Gulf Coast Segment and the Houston Lateral, although construction is planned for winter months, the prevailing climate would not require the use of special winter construction techniques.

A list of typical equipment to be used during construction is presented in Table 2.3.2-1. Actual equipment used would depend on the construction activity and specific equipment owned or leased by the construction contractors selected.

**TABLE 2.3.2-1
Minimum Equipment Required for Selected Construction Activities**

Activity	Minimum Equipment
Clearing and grading	6 D8 dozers 1 – 330 trackhoe (thumb and hoe pack) 6 – 345 trackhoes 2 D8 with ripper attachment 1 – 140 motor grader
Trenching	6 – 345 trackhoes 1 – 345 trackhoe with hammer 4 ditching machines
Stringing, bending, and welding	2 – 345 trackhoes vacuum fitted (1 at pipe yard, 1 at ROW) 1 – D7 tow cat 15 string trucks 2 bending machines 10 – 572 side booms 10 – 583 side booms 6 – automatic welding machines with end-facing machine 8 ultrasonic testing units 1 NDE unit 2 heat rings 4 coating rings 3 sled with generators
Lowering in and backfilling	3 – 345 trackhoes (1 equipped with long neck) 5 – 583 side booms 2 padding machines 3 D8 dozers
Tie-ins to the mainline (Six tie-in crews per spread; equipment listed if for each crew)	4 welding rigs 7 – 572 side booms 2 ultrasonic testing units 2 heat rings 2 coating rings 1 sled with generators 2 – 345 trackhoes (1 equipped with shaker bucket) 2 – 583 side booms 1 D8 dozer

TABLE 2.3.2-1 Minimum Equipment Required for Selected Construction Activities	
Activity	Minimum Equipment
Cleanup and restoration	6 D8 dozers 3 – 345 backhoes 2 tractors with mulcher spreaders (seed and reclamation)
Equipment deployed for each spread	100 pickup trucks 2 water trucks 2 fuel trucks 7 equipment low-boys 7 flat bed trucks 5 – 2-ton boom truck

In addition to the equipment listed in Table 2.3.2-1, each spread would have 450 to 500 construction personnel and 30 inspection personnel. Normal construction activities would be conducted during daylight hours, with the following exceptions:

- Completion of critical tie-ins on the ROW would likely occur after daylight hours. Completion requires tie-in welds, non-destructive testing, and sufficient backfill to stabilize the ditch.
- HDD operations (see Section 2.3.3.5 for additional information on the HDD method) may be conducted after daylight hours, if determined by the contractor to be necessary to complete a certain location. In some cases, that work may be required continuously until the work is completed; this may last one or more 24-hour days. Such operations may include drilling and pull-back operations, depending upon the site and weather conditions, permit requirements, schedule, crew availability, and other factors.
- Hydrostatic testing operations may be conducted after daylight hours if determined by the contractor to be necessary to complete a certain location. In some cases, that work may be required continuously until the work is completed; this activity may take place for 24 continuous hours or longer. While not anticipated in typical operations, certain work may be required after the end of daylight hours due to weather conditions, for safety, or for other Project requirements.

2.3.2.1 Surveying and Staking

Before construction begins, the construction ROW boundaries and any additional temporary workspace areas would be marked to identify the limits of the approved work area. The locations of approved access roads and existing utility lines would be flagged. Wetland boundaries and other environmentally sensitive areas would be marked or fenced for protection. A survey crew would stake the centerline of the trench and any buried utilities along the ROW.

Some landowner fences would be crossed or paralleled by the construction ROW, requiring fence cutting and modifications. Each fence would be braced and secured before cutting to prevent the fence from weakening or slacking. Openings created in the fences would be temporarily closed when construction crews leave the area to contain livestock. In addition, gaps through natural livestock barriers would be fenced according to landowners' or land managers' requirements. If livestock is present, temporary gates and fences would be installed.

2.3.2.2 Clearing and Grading

Prior to vegetation removal along slopes leading to wetlands and riparian areas, temporary erosion control measures such as silt fences or straw bales would be installed. The work area would be cleared of vegetation, including crops and obstacles such as trees, logs, brush, or rocks.

Grading would be performed where necessary to provide a reasonably level work surface or where required by landowners or land managers. Where the ground is relatively flat and does not require grading, rootstock would be left in the ground. More extensive grading would be required in steep slope areas to safely construct the pipeline along ROW. Where grading occurs and topsoil is present, topsoil would be removed from the entire area to be graded and stored separately from the subsoil.

2.3.2.3 Trenching

Trenching may be carried out before or after stringing, bending and welding (see Section 2.3.2.4) depending upon several factors such as soil characteristics, water table, presence of drain tiles, and weather conditions at the time of construction.

In areas of rocky soils or bedrock, tractor-mounted mechanical rippers or rock trenchers would fracture the rock prior to excavation. In areas where topsoil segregation would be required, the actual depth of topsoil would be removed up to a maximum depth of 12 inches and segregated. In most areas where soil would be removed from only the trench, topsoil would be piled on the near-side of the trench and subsoil on the far side of the trench. A “triple lift” method would be used in areas where deep soils would be excavated, primarily over the pipeline trench in cultivated fields to minimize impacts to agricultural production. This method would involve stockpiling three different soil horizons, including the topsoil horizon, as described in Section 3.2.2.1. This separation of topsoil from subsoil would allow for proper restoration of the soil during the backfilling process. Where soil is removed from both the trench and the spoil side, topsoil would be stored on the near-side of the construction ROW edge, and the subsoil on the spoil-side of the trench.

These procedures separating topsoil would reduce the potential for mixing of subsoil and topsoil. In addition, the spoil piles would be spaced to accommodate storm water runoff. Typical soil separation methods are illustrated in Figures 2.1.2-1 through 2.1.2-3.

On agricultural land, rocks that are exposed on the surface due to construction activity would be removed from the ROW prior to and after topsoil replacement. Rock removal would also occur in rangeland to ensure that the productive capability of the land is maintained. In some landscapes, thin soils overlay bedrock, or exposed bedrock exists at the surface. In these cases, rock would be replaced to the extent practicable. Clearing of rocks could be carried out either manually or with a mechanical rock picker and topsoil would be preserved. Rocks that are similar in size to those occurring in the undisturbed landscape would be left in place to the extent practicable. Rock removed from the ROW would be either hauled away for disposal in appropriate facilities or placed in a location acceptable to the landowner.

Trench excavation would typically be to depths of between 7 and 8 feet, with a trench width of approximately 4 to 5 feet. In most areas, there would be a minimum of 4 feet of cover over the pipeline after backfilling. The depth of burial would be consistent with PHMSA Special Condition 19 which states the following:

“19) Depth of Cover: Keystone shall construct the pipeline with soil cover at a minimum depth of forty-eight (48) inches in all areas, except in consolidated rock. The minimum depth in consolidated rock areas is thirty-six (36) inches.”

In addition, the depth of burial at waterbodies, ditches, drainages, and other similar features would be 60 inches, except in rocky areas where the minimum burial depth would be 36 to 48 inches. Where major waterbodies are crossed using the HDD method, the depth from the streambed to the top of the pipe would be substantively greater than 60 inches. Depths of cover over the pipe along the proposed route in areas of normal excavation and in rocky excavation areas are listed in Table 2.3.2-2.

TABLE 2.3.2-2 Minimum Pipeline Cover		
Location	Depth Below Ground Surface in Inches	
	Normal Excavation	Rock Excavation
Most areas	48	36
All waterbodies	60	36
Dry creeks, ditches, drains, washes, gullies, etc.	60	36
Drainage ditches at public roads and railroads	60	48

Special Condition 19 also requires that Keystone maintain the depth of cover after construction is completed. Specifically, the condition states the following:

“Keystone shall maintain a depth of cover of 48 inches in cultivated areas and a depth of 42 inches in all other areas.”

Some commenters recommended that Keystone install “warning tape” over the pipeline to alert excavators to the presence of the pipeline. Keystone would comply with the following stipulations of PHMSA Special Condition 19 that relates to the use of warning tape.

“In cultivated areas where conditions prevent the maintenance of forty-eight (48) inches of cover, Keystone must employ additional protective measures to alert the public and excavators to the presence of the pipeline. The additional measures shall include:

- a) Placing warning tape and additional line-of-sight pipeline markers along the affected pipeline segment,
- b) In areas where threats from chisel plowing or other activities are threats to the pipeline, the top of the pipeline must be installed and maintained at least one foot below the deepest penetration above the pipeline, not to be less than 42-inches of cover.”

2.3.2.4 Pipe Stringing, Bending, and Welding

After the pipe sections are bent, the pipeline joints would be lined up and held in position until welding. The joints would be welded together to create long “strings” that would be placed on temporary supports. All welds would be inspected using non-destructive radiographic, ultrasonic, or other methods that provide an equivalent or better level of safety as those required in 49 CFR Part 195. All aspects of welding, including reporting, would be conducted consistent with the requirements of 49 CFR 195.228 and PHMSA Special Conditions 4, 5, 6, 12, 18, and 20 (Appendix U). Welds that do not meet established specifications would be repaired or removed and replaced. Once the welds are approved, a protective epoxy coating would be applied to the welded joints to inhibit corrosion.

2.3.2.5 Installing and Backfilling

Prior to installing the pipe into the trench, the trench would be cleared of rocks and debris that might damage the pipe or the pipe coating. If water has entered the trench, dewatering may be required prior to installation. Discharge of water from dewatering would be accomplished in accordance with applicable discharge permits. On sloped terrain, trench breakers (e.g., stacked sand bags or foam) would be installed in the trench at specified intervals to prevent subsurface water movement along the pipeline.

In some cases sand or gravel padding material may be placed in the bottom of the trench to protect the pipeline from damage during installation. In no case would topsoil be used as a padding material. In areas of rocky soils or bedrock, the bottom of the trench would be padded with borrow material such as sand or gravel. Where rock occurs within the trench perimeter, abrasion resistant coatings or rock shields would be used to protect the pipe prior to installation.

The pipeline would be lowered into the trench and the trench would first be backfilled using the excavated subsoil material. In rocky areas, excavated rock would be used to backfill the trench to the top of the existing bedrock profile. After the initial backfilling, topsoil would be returned to its original position over the trench.

2.3.2.6 Hydrostatic Testing

In addition to hydrostatic testing at the pipe mills, the pipeline would be cleaned and hydrostatically tested prior to putting the pipe into service and after backfilling and all construction work that could directly affect the pipe is complete. The testing would be conducted in pipeline sections approximately 30 to 50 miles long. Hydrostatic testing would provide assurance that the system is capable of withstanding the maximum operating pressure and would be conducted in accordance with the regulatory requirements of 49 CFR Part 195, Subpart E (Pressure Testing) and the stipulations in PHMSA Special Conditions 5, 20, 22, and 23 (Appendix U). The process would be conducted as follows:

- Isolate the pipe section being tested with test manifolds;
- Fill the section with water;
- Pressurize the section to a pressure that would produce a hoop stress of a minimum of 100 percent of the specified minimum yield strength for the mainline pipe and 1.39 times the maximum operating pressure for pump stations; and
- Maintain that pressure for a period of 8 hours.

2.3.2.7 Pipe Geometry Inspection, Final Tie-ins, and Commissioning

After hydrostatic testing is complete, the pipeline would be dewatered and inspected using an electronic caliper (geometry) pig to check for dents or other deformations and where appropriate, pipe sections would be replaced in accordance with the requirements of 49 CFR 195 and the Special Conditions in Appendix U. The final pipeline tie-ins would then be welded and inspected.

After the final tie-ins are complete and inspected, the pipeline would be commissioned through the verification of proper installation and function of the pipeline and appurtenant systems, including control and communication equipment, based on the requirements of 49 CFR 195 and the relevant PHMSA Special Conditions.

2.3.2.8 Cleanup and Restoration

Cleanup would include the removal of construction debris, final contouring, and installation of erosion control features. The cleanup process would begin as soon as possible after backfilling but the timing would be dependent on weather conditions. Preliminary cleanup would be completed within approximately 20 days after the completion of backfilling assuming appropriate weather conditions prevail. Removed construction debris would be disposed in existing, permitted disposal facilities in accordance with relevant federal, state, and local regulations.

Reseeding of the ROW would occur as soon as possible after completion of cleanup to stabilize soil. Procedures would depend on weather and soil conditions and would follow recommended rates and seed mixes provided by the landowner, the land management agency, or the NRCS. Access to the permanent easement would be restricted using gates, boulders, or other barriers to minimize unauthorized access by all-terrain vehicles, if requested by the landowner.

All existing fencing and grazing structures, such as fences, gates, irrigation ditches, cattle guards, and reservoirs would be repaired to pre-construction conditions or better upon completion of construction activities.

Pipeline markers would be provided for identification of the pipeline location for safety purposes in accordance with the requirements of 49 CFR 195.410 (Line Markers) and PHMSA Project-specific Special Condition 40 (see Appendix U), including the following:

- Pipeline markers would be installed on both sides of all highways, roads, road ROWs, railroads, and waterbody crossings and in areas where the pipeline is buried less than 48 inches;
- Pipeline markers would be made from industrial strength materials to withstand abrasion from wind and damage from cattle;
- Pipeline markers would be installed at all fences;
- Pipeline markers would be installed along the ROW to provide line-of-sight marking of the pipeline, providing it is practical to do so and consistent with the type of land use, such that it does not hinder the use of the property by the landowner. Pipeline markers would be installed at all angle points, and at intermediate points, where practical, so that from any marker, the adjacent marker in either direction would be visible;
- Consideration would be given to installing additional markers, except where they would interfere with land use (e.g., farming);
- Aerial markers showing identifying numbers would be installed at approximately 5-mile intervals; and
- At each MLV site and pump station, signs would be installed and maintained on the perimeter fence where the pipeline enters and exits the fenced area.

Markers would identify the owner of the pipeline and convey emergency contact information. Special markers providing information and guidance to aerial patrol pilots also would be installed. The markers would be maintained during operating life of the proposed Project.

2.3.2.9 Post-Construction Reclamation Monitoring and Response

The ROW would be inspected after the first growing season to determine the success of revegetation and noxious weed control. Eroded areas would be repaired and areas that were unsuccessfully re-established would be revegetated by Keystone or Keystone would compensate the landowner for reseeded. The

CMR Plan (Appendix B) provides information on revegetation and weed control procedures that Keystone would incorporate into the proposed Project.

2.3.3 Special Pipeline Construction Procedures

Special construction techniques would be used when crossing roads, highways and railroads; pipeline, utility, and other buried feature crossings; steep terrain; unstable soils; perennial waterbodies; wetlands; areas that require ripping; and residential and commercial areas. These special techniques are described below.

2.3.3.1 Road, Highway, and Railroad Crossings

Construction across paved roads, highways, and railroads would be in accordance with the requirements of the appropriate road and railroad crossing permits and approvals. In general, all major paved roads, all primary gravel roads, all highways, and all railroads would be crossed by boring beneath the road or railroad, as shown in Figure 2.3.3-1. Boring would result in minimal or no disruption to traffic at road or railroad crossings. Each boring would take 1 to 2 days for most roads and railroads, and 10 days for long crossings such as interstate or 4-lane highways.

Initially, a pit would be excavated on each side of the feature; boring equipment would be placed in the pit and a hole would be bored under the road at least equal to the diameter of the pipe and a prefabricated pipe section would be pulled through the borehole. For long crossings, sections would be welded onto the pipe string before being pulled through the borehole.

If permitted by local regulators and landowners, smaller gravel roads and driveways would likely be crossed using an open-cut method that would typically take between 1 and 2 days to complete. This would require temporary road closures and the establishment of detours for traffic. If no reasonable detour is feasible, at least one lane of traffic would be kept open in most cases. Keystone would post signs at these open-cut crossings and would implement traffic control plans to reduce traffic disturbance and protect public safety. Section 2.2.7.5 provides additional information on roadway safety, maintenance, and repair.

2.3.3.2 Pipeline, Utility, and Other Buried Feature Crossings

Keystone and its pipeline contractors would comply with USDOT regulations, utility agreements, and industry BMPs with respect to utility crossing and separation specifications. One-call notification would be made for all utility crossings to identify utilities. Similarly, private landowners would be notified of planned construction activities so that buried features, such as irrigation systems and other water lines, could be avoided or replaced. Prior to construction, each rancher with a stock watering or irrigation system or other water lines would be asked to provide the location of any waterlines in the construction area. The location of these waterlines would be documented and Keystone would lower some waterlines prior to construction. In the case of existing buried oil or gas pipelines, the owner of the facility would be asked to provide information on the locations of pipes in the construction area. Metallic pipelines would be physically located by a line locating crew prior to construction.

Unless otherwise specified in a crossing agreement, the contractor would excavate to allow installation of the proposed Project pipeline across the existing pipeline or utility with a minimum clearance of 12 inches. The clearance distance would be filled with sandbags or suitable fill material to maintain the clearance. Backfill of the crossing would be compacted in lifts to ensure continuous support of the existing utility.

For some crossings, the owner of the utility or buried feature may require the facility to be excavated and exposed by their own employees prior to the Keystone contractor getting to the location. In those cases, Keystone would work with owners to complete work to the satisfaction of the owner. Where the owner of the utility does not require pre-excavation, generally, the pipeline contractor would locate and expose the utility before excavating the trench.

2.3.3.3 Steep Terrain

Steep slopes traversed by the proposed route would be graded to reduce slope angles, thus allowing safer operation of construction equipment and reducing the degree of pipe bending required. In areas where the pipeline route crosses side slopes, cut-and-fill grading may be employed to obtain a safe working terrace. Prior to cut-and-fill grading on steep terrain, topsoil would be stripped from the ROW and stockpiled. If soil and slope conditions permit, soil from the high side of the ROW would be excavated and moved to the low side to create a safer and more level working surface. After pipeline installation, soil from the low side of the ROW would be returned to the high side and the contour of the slope would be restored to its pre-construction condition to the degree practicable.

Temporary sediment barriers, such as silt fences and straw bales, would be installed where appropriate to prevent erosion and siltation of wetlands, waterbodies, or other environmentally sensitive areas. During grading, temporary slope breakers consisting of mounded and compacted soil would be installed across the ROW. In the cleanup phase, permanent slope breakers would be installed where appropriate. Section 4.5 of the CMR Plan (Appendix B) presents additional information on the use of sediment barriers and slope breakers.

After regrading and installation of erosion control devices, seed would be applied to steep slopes and mulch consisting of hay or non-brittle straw would be placed on the ROW, or the ROW would be protected with erosion control geofabrics. Where appropriate to avoid animal entanglement, geofabric mesh size would be 2 inches or greater. Sediment barriers would be maintained across the ROW until permanent vegetation is established. Additional temporary workspaces may be required for storage of graded material and/or topsoil during construction.

2.3.3.4 Unstable Soils

Special construction techniques and environmental protection measures would be applied to areas with unstable soils, such as those within the Sand Hills region of South Dakota and Nebraska, and to areas with high potential for landslides, erosion, and mass wasting. Construction in these areas could require additional temporary workspace areas.

Topsoil piles would be protected from erosion through matting, mulching, watering, or tackifying to the extent practicable. Photodegradable matting would be placed on steep slopes or areas prone to extreme wind exposure, such as north- or west-facing slopes and ridge tops. Biodegradable pins would be used in place of metal staples to hold the matting in place.

Reseeding would be carried out using native seed mixes that are certified noxious weed-free, if possible. Land imprinting may be employed to create impressions in the soil to reduce erosion, improve moisture retention, and create micro-sites for seed germination. Keystone would work with landowners to evaluate fencing the ROW from livestock, or alternatively, to provide compensation if a pasture needs to be rested until vegetation can become established.

2.3.3.5 Waterbody Crossings

In the final design phase of the proposed Project, perennial waterbody crossings for the proposed pipeline would be assessed by qualified personnel with respect to the potential for channel aggradation or degradation and lateral channel migration. The level of assessment for each crossing would vary based on the professional judgment of the qualified design personnel. The pipeline would be installed as necessary to address any hazards identified by the assessment. The pipeline would be installed at the design crossing depth for at least 15 feet beyond the design lateral migration zone, as determined by qualified personnel. The design of the crossings also would include the specification of appropriate stabilization and restoration measures. The actual crossing method employed at a perennial stream would depend on permit conditions from USACE and other relevant regulatory agencies, as well as additional conditions that may be imposed by landowners or land managers at the crossing location. Appendices D and E provide Site Specific Waterbody Crossing Plans and Waterbody Crossing Tables, respectively. Additional information on the types of crossing methods proposed for use on the proposed Project is presented in the subsections below.

In addition to the proposed pipeline crossings of waterbodies, there would be temporary equipment bridges installed across many waterways. Prior to the start of clearing for the proposed Project pipeline along each pipeline construction spread, temporary bridges (e.g., subsoil fill over culverts, timber mats supported by flumes, railcar flatbeds, or flexi-float apparatus) would be installed across all perennial waterbodies to allow construction equipment to cross with reduced disturbance. Clearing crews would be allowed only one pass through the waterbodies prior to temporary bridge construction. All other construction equipment would be required to use the bridges.

Proposed Waterbody Crossing Methods

Waterbodies would be crossed using one of four different open-cut methods or the HDD method. These waterbody crossing methods are described below.

Open-Cut Crossing Methods

For most waterbodies to be crossed by the proposed Project, one of the open-cut methods listed below would be used:

- Non-flowing dry open-cut crossing method (for waterbodies that do not have a perceptible flow at the time of construction);
- Flowing open-cut crossing method;
- Dry-flume open-cut method; or
- Dry dam-and-pump open-cut method.

The trenching, pipeline installation, and backfilling methods used for these types of crossings would be similar to the cross-country construction methods described above.

Non-Flowing and Flowing Open-Cut Crossing Methods

The non-flowing open-cut method would be used for all waterbodies with no visible flow at the time of construction. Prior to construction, timber matting and riprap would be installed in the entire area of the crossing to minimize compaction from equipment. The pipe section would be fabricated adjacent to the stream or in a staging area, the stream would be trenched, the pipe would be lowered into the trench, and the trench would be backfilled. Detail 11 of the CMR Plan (Appendix B) is an illustration of a typical

open-cut crossing method for non-flowing waterbodies. After installation, the timber mats would be removed, the grade would be restored to pre-construction condition, topsoil would be replaced (unless saturated conditions exist), and permanent erosion control devices would be installed.

If there is flow at the time of construction, the flowing open-cut method would be used and the trench would be excavated through flowing water. Backhoes operating from one or both banks would excavate the trench within the streambed while water continues to flow through the construction work area (see Detail 12 of the CMR Plan [Appendix B]). In wider rivers, in-stream operation of equipment may be necessary. Keystone would trench through the stream, lower in a pipe that is weighted for negative buoyancy, then backfill. The need for negative buoyancy would be determined by detailed design and site-specific considerations at the time of construction. Material excavated from the trench generally would be placed at least 10 feet away from the water's edge unless stream width exceeds the reach of the excavation equipment. Sediment barriers would be installed where necessary to prevent excavated spoil from entering the water. Hard or soft trench plugs would be placed to prevent the flow of water into the upland portions of the trench. After installation, the grade would be restored to pre-construction condition, topsoil would be replaced (unless saturated conditions exist), and permanent erosion control devices would be installed.

For both crossing types, pipe segments for each crossing would be welded and positioned adjacent to the waterbody. After the trench is excavated, the pipeline segment would be carried, pushed, or pulled across the waterbody and positioned in the trench. The trench would be backfilled with native material or with imported material if required by permits.

Keystone would minimize the time of in-stream construction to reduce impacts to waterbody channel and banks. For minor waterbodies (less than 10 feet wide at the water's edge), the trenching and backfill of the crossing would typically require no more than 24 hours; intermediate waterbodies (10 to 100 feet wide) would typically require no more than 48 hours. Major waterbodies (more than 100 feet wide) would be crossed as quickly as possible. It is possible that the time required to accomplish the crossings of major waterbodies could exceed 48 hours. To the extent practicable, non-flowing open-cut crossings would be the preferred crossing method.

Dry-Flume Open-Cut Method

Keystone would use the dry-flume method on selected environmentally sensitive waterbodies where technically feasible. The dry-flume method is used for sensitive, relatively narrow waterbodies free of large rocks and bedrock at the trenchline and with a relatively straight channel across the construction ROW. The dry-flume method generally is not appropriate for wide, deep, or heavily flowing waterbodies. Use of this method involves installing dams upstream and downstream of the construction area and installing one or more pipes (flumes) that would extend along the course of the waterbody and through both dams. Streamflow would be carried through the construction area by the flume pipe(s).

Keystone would install flumes with sufficient capacity to transport the maximum flows that could be generated seasonally within the waterbody. The flumes, typically 40 to 60 feet long, would be installed before trenching and aligned to prevent impounding of water upstream of the construction area or to cause back-erosion downstream.

The upstream and downstream ends of the flumes would be incorporated into dams made of sandbags and plastic sheeting (or equivalent material). Upstream dams would be installed first and would funnel streamflow into the flumes. Downstream dams then would be constructed to prevent water from flowing back into the area to be trenched. The flumes would remain in place during pipeline installation, backfilling, and streambank restoration.

Prior to trenching, the area between the dams typically would be dewatered. Backhoes working from one or both banks, or from within the isolated waterbody bed, would excavate the trench across the waterbody and under the flume pipes. Excavated material would be stockpiled on the upland construction ROW at least 10 feet from the water's edge or in the extra workspaces. Sediment containment devices, such as silt fences and straw bales, would be installed to contain the excavated material and to minimize the potential for sediment to migrate into the waterbody.

After the trench is excavated to the proper depth, a prefabricated section of pipe would be positioned and lowered into the trench. The trench then would be backfilled with the excavated material from the stream unless otherwise specified in stream crossing permits. Prior to removing the dams and flume pipes and restoring streamflow, water that accumulated in the construction area would be pumped into a straw bale structure or similar dewatering device, and the bottom contours of the streambed and the streambanks would be restored as close as practical to pre-construction contours.

Dry Dam-and-Pump Open-Cut Method

As an alternative to the dry-flume crossing method, Keystone could use the dry dam-and-pump method on selected environmentally sensitive waterbodies where practical. The dry dam-and-pump method is similar to the dry-flume method except that pumps and hoses would be used instead of flumes to move water around the construction work area. When using this method, Keystone would initiate pumping while the dams are being installed to prevent interruption of streamflows. Where necessary to prevent scouring of the waterbody bed or adjacent banks, the downstream discharge would be directed into an energy-dissipation device or concrete weight. The pump capacity would be greater than the anticipated flow of the waterbody being crossed. As with the dry-flume method, trenching, pipe installation, and backfilling would be done while water flow is maintained for all but a short reach of the waterbody at the actual crossing location. Once backfilling is completed, the stream banks would be restored and stabilized and the pump hoses would be removed.

Horizontal Directional Drilling Method

As currently proposed, the HDD crossing method would be used at the waterbody crossings listed in Table 2.3.3-1. The HDD method could also be used to bore beneath terrestrial areas that contain special resources that require avoidance.

TABLE 2.3.3-1 Waterbodies Crossed Using the Horizontal Directional Drilling Method			
Segment	Waterbody	Number of Crossings	Approximate Milepost
Steele City	Milk River	1	82.9
	Missouri River	1	89.2
	Yellowstone River	1	196.4
	Little Missouri River	1	292.1
	Cheyenne River	1	426.1
	White River	1	537.2
	Niobrara River	1	615.5
	Cedar River	1	697.3
	Loup River	1	740.7
	Platte River	1	756.3
Gulf Coast	Deep Fork	1	22.2
	North Canadian River	1	38.6
	Little River	1	70.4

**TABLE 2.3.3-1
Waterbodies Crossed Using the Horizontal Directional Drilling Method**

Segment	Waterbody	Number of Crossings	Approximate Milepost
	Canadian River	1	74.1
	Fronterhouse Creek	1	122.6
	Clear Boggy Creek	1	127.1
	Red River	1	155.7
	Bois D'Arc Creek	1	162.0
	North Sulphur River	1	190.8
	South Sulphur River	1	201.8
	White Oak Creek	1	212.8
	Big Cypress Creek	1	228.4
	Private Lake	1	254.8
	Big Sandy Creek	1	256.9
	Sabine River	1	263.5
	East Fork of Angelina River	1	313.3
	Angelina River	1	334.2
	Neches River and Fiberboard Lake	1	368.6
	Menard Creek	1	416.3
	Pine Island Bayou	1	448.9
	Lower Neches Valley Canal Authority	1	461.8
	Lower Neches Valley Canal Authority	1	462.5
	Willow Marsh Bayou	1	469.9
	Canal	1	471.0
	Hillebrandt Bayou	1	473.8
Houston Lateral	Turkey Creek Marsh	1	17.7
	Trinity River	1	22.8
	Cedar Bayou	1	35.6
	San Jacinto River	1	43.3

Waterbodies Keystone has considered for HDD include commercially navigable waterbodies, waterbodies wider than 100 feet, waterbodies with terrain features that prohibit open crossing methods, waterbodies adjacent to features such as roads and railroads, and sensitive environmental resource areas. Additional HDD crossings could be incorporated into the proposed Project as a result of resource agency, landowner, or land manager concerns, as well as due to construction related issues.

The HDD method involves drilling a pilot hole under the waterbody and banks, then enlarging the hole through successive ream borings with progressively larger bits until the hole is large enough to accommodate a pre-welded segment of pipe. Throughout the process of drilling and enlarging the hole, a water-bentonite slurry would be circulated to lubricate the drilling tools, remove drill cuttings, and provide stability to the drilled holes. Pipe sections long enough to span the entire crossing would be staged and welded along the construction work area on the opposite side of the waterbody and then pulled through the drilled hole. The welded drill string would be hydrostatically tested for 4 hours prior to being pulled into place. Depending on the angle of approach of the pipeline alignment to the water crossing, a “false ROW” may need to be cleared on the pull back side to allow pipe placement at the appropriate angle to the waterbody. Keystone has created Site Specific Waterbody Crossing Plans (Appendix D) that describe the procedures to be used at each perennial waterbody crossed using the HDD method.

Several commenters on the draft EIS were concerned that the HDD method might damage the pipe or the protective coating of the pipe. Keystone would use industry standard procedures to ensure pipe and coating integrity are maintained during HDD installations. This includes application of an abrasion resistant overcoat to the FBE coating on the pipe joints designated for HDDs. This overcoat prevents damage to the corrosion resistant FBE coating as the pipe is pulled through the bored hole. During HDD operations, the hole that is reamed to allow the pipeline to be pulled through is much larger than the pipe diameter (approximately a 42-inch-diameter hole or larger for the 36-inch-diameter pipe). As noted above, bentonite drilling mud would be used to reduce friction and provide lubrication and buoyancy for the pipe during the pull back, assuring minimal contact with the walls of the drill hole. After installation, Keystone would conduct cathodic protection and in-line inspection surveys to determine if any damage may have resulted to the pipe coating during the construction process.

Procedures to Avoid or Minimize Impacts of Waterbody Crossings

Equipment refueling and lubricating would take place in upland areas 100 feet or more from the water. If equipment refueling and lubricating becomes necessary within 100 feet of a perennial waterbody, the SPCC Plan would be adhered to relative to the handling of fuel and other hazardous materials.

To minimize the potential for sediment runoff during clearing, sediment barriers such as silt fences and staked straw bales would be installed and maintained on drainages in the ROW and adjacent to waterbodies and within additional temporary workspace areas. Silt fences and straw bales located across the working side of the ROW would be removed during the day when vehicle traffic is present and would be replaced each night. Drivable berms may be installed across the ROW instead of silt fences or straw bales.

After pipeline installation, stream banks would be restored to preconstruction contours or to a stable configuration. Stream banks would be seeded for stabilization, and covered with mulch or covered with erosion control fabric in accordance with the CMR Plan (Appendix B) and applicable state and federal permit conditions. Stream banks would be temporarily stabilized within 24 hours of completing in-stream construction. Sediment barriers, such as silt fences, straw bales, or drivable berms, would be maintained across the ROW at all stream or other waterbody approaches until permanent vegetation becomes established. Temporary equipment bridges would be removed after construction.

2.3.3.6 Wetland Crossings

Construction across wetlands would be similar to typical conventional upland cross-country construction, with modifications to reduce the potential for effects to wetland hydrology and soil structure. The wetland crossing methods used would depend largely on the stability of the soils at the crossing location at time of construction.

Over most of the ROW, clearing of vegetation in wetlands would be limited to flush-cutting of trees and shrubs and their subsequent removal from wetland areas. Stump removal, grading, topsoil segregation, and excavation would be limited to the area immediately over the trench line. During clearing, sediment barriers, such as silt fences and staked straw bales, would be installed and maintained on slopes adjacent to saturated wetlands and within additional temporary workspace areas as necessary to reduce sediment runoff. Tall-growing vegetation would be allowed to regrow in riparian areas in the temporary ROW, but not in the permanent ROW.

In areas with unsaturated soils that are able to support construction equipment without equipment mats, construction would occur in a manner similar to conventional upland cross-country construction. Topsoil removed from the trench line would be segregated and replaced after backfilling the trench with subsoil.

In areas where wetlands overlie rocky soil, the pipe would be padded with rock-free soil or sand before backfilling with native bedrock and soil.

Where wetland soils are saturated or inundated, the pipeline could be installed using the push-pull technique. The push-pull installation process would involve stringing and welding the pipeline outside of the wetland, and excavating and backfilling the trench using a backhoe supported by equipment mats or timber riprap. Trench breakers would be installed where necessary to prevent the subsurface drainage of water from wetlands. The pipeline segment would be installed in the wetland by equipping it with floats and pushing or pulling it across the water-filled trench. After the pipeline is floated into place, the floats would be removed and the pipeline would sink into place. Most pipes installed in saturated wetlands would be coated with concrete or installed with set-on weights to provide negative buoyancy. Where topsoil has been segregated from subsoil, the subsoil would be backfilled first followed by the topsoil. Restoration of contours would be accomplished during backfilling because little or no grading would occur in wetlands.

Construction equipment working in saturated wetlands would be limited to that area essential for clearing the ROW, excavating the trench, welding and installing the pipeline, backfilling the trench, and restoring the ROW. In areas where there is no reasonable access to the ROW except through wetlands, non-essential equipment would be allowed to travel through wetlands only if the ground is firm enough or has been stabilized to avoid rutting. Additional temporary workspace areas would be required on both sides of wide saturated wetlands to stage construction, weld the pipeline, and store materials. These additional temporary workspace areas would be located in upland areas a minimum of 10 feet from the wetland edge. This distance is that a standard backhoe can reach and would avoid the need for additional equipment to transfer soil farther from the wetland.

Equipment mats, timber riprap, gravel fill, geotextile fabric, and straw mats would be removed from wetlands after backfilling except in the travel lane to allow continued, controlled access through the wetland until the completion of construction. Upon the completion of construction, these materials would be removed. Topsoil would be replaced to the original ground level leaving no crown over the trench line. Excess excavated material would be removed from the wetland and spread along the upland ROW, placed in a location as requested by a landowner, or disposed of at an existing authorized landfill.

Where wetlands are located at the base of slopes, permanent slope breakers would be constructed across the ROW in upland areas adjacent to the wetland boundary. Temporary sediment barriers would be installed where necessary until revegetation of adjacent upland areas is successful. Once revegetation is successful, sediment barriers would be removed from the ROW and disposed of at an existing authorized landfill.

If equipment refueling and lubricating becomes necessary within 100 feet of a wetland, the SPCC Plan would be adhered to relative to the handling of fuel and other hazardous materials.

2.3.3.7 Ripping

In areas where bedrock is within 84 inches (7 feet) of the surface and is expected to be dense or highly stratified, ripping could be required. Ripping would involve tearing up the rock with mechanical excavators. During ripping, Keystone would take extreme care to avoid damage to underground structures, cables, conduits, pipelines, and underground watercourses.

Keystone anticipates that blasting would not be required. If blasting is necessary, Keystone would prepare and file a blasting plan with the appropriate agencies.

2.3.3.8 Construction in Residential and Commercial Areas

Keystone would prepare site-specific construction plans to address the potential impacts of construction on residential and commercial structures near the construction ROW. Areas containing buildings within 25 feet and 500 feet of the construction ROW are listed in Table 2.3.3-2. Information on the types of structures present is provided in Section 3.9 (Land Use). Additional construction and environmental protection measures for structures near the construction ROW are described in the CMR Plan (see Appendix B).

TABLE 2.3.3-2 Structures Located Within 25 Feet and 500 Feet of the Construction ROW			
Segment and State	County	Structures Within 25 Feet of Construction ROW (Number)	Structures Within 500 Feet of Construction ROW (Number)
Steele City Segment			
Montana	Phillips	0	9
	Valley	2	38
	McCone	2	21
	Dawson	3	21
	Prairie	0	3
	Fallon	2	25
South Dakota	Harding	3	19
	Butte	0	0
	Perkins	1	3
	Meade	2	22
	Pennington	0	0
	Haakon	4	26
	Jones	0	3
	Lyman	1	9
	Tripp	4	14
Nebraska	Keya Paha	2	3
	Rock	0	2
	Holt	3	11
	Garfield	0	0
	Wheeler	1	4
	Greeley	0	8
	Boone	0	0
	Nance	0	11
	Merrick	7	25
	Hamilton	1	5
	York	1	28
	Fillmore	1	22
	Saline	1	13
	Jefferson	0	18

TABLE 2.3.3-2 Structures Located Within 25 Feet and 500 Feet of the Construction ROW			
Segment and State	County	Structures Within 25 Feet of Construction ROW (Number)	Structures Within 500 Feet of Construction ROW (Number)
Cushing Extension			
Kansas	0	0	0
Gulf Coast Segment			
Oklahoma	Lincoln	4	91
	Creek	0	0
	Okfuskee	7	61
	Seminole	6	51
	Hughes	7	88
	Coal	1	56
	Atoka	1	50
	Bryan	2	51
Texas	Fannin	0	1
	Lamar	7	89
	Delta	6	41
	Hopkins	7	78
	Franklin	4	68
	Wood	2	140
	Upshur	7	31
	Smith	16	258
	Cherokee	1	33
	Rusk	10	44
	Nacogdoches	5	123
	Angelina	2	80
	Polk	9	112
	Liberty	4	76
	Hardin	5	15
	Jefferson	6	221
Houston Lateral (Texas)			
	Liberty	6	60
	Chambers	0	3
	Harris	4	41

2.3.4 Aboveground and Ancillary Facilities Construction Procedures

2.3.4.1 Pump Station Construction

Construction at each new pump station would begin with clearing of vegetation and removal of topsoil. After that the site would be graded as necessary to create a level working surface for the movement of construction vehicles and to prepare the area for building foundations. Foundations would be installed for the electrical equipment shelter (EES) and the pump equipment shelter. The EES would include electrical systems, communication, and control equipment. The structures to support the pumps, manifolds, pig

receiving and pig launching equipment, densitometers (where present), and associated facilities would then be erected. This would include installation of a block valve into the mainline as well as two MLV block valves: one would be installed on the suction piping of the pumps and one would be installed on the discharge piping of the pumps as required by 49 CFR 195.260.

The piping, both aboveground and below ground, would be installed and pressure tested using the methods employed for the main pipeline. After successful testing, the piping would be tied into the main pipeline. Piping installed below grade would be coated for corrosion protection as required by 49 CFR 195 Subpart H (Corrosion Control) and the applicable Project-specific PHMSA special conditions. In addition, all below-grade facilities would be protected by a cathodic protection system as required by Subpart H and the applicable Project-specific PHMSA special conditions. Pumps, controls, and safety devices would be checked and tested to ensure proper system operation and activation of safety mechanisms before being put into service. After hydrostatic testing of the below-grade equipment, the site would be graded and surfaced with gravel and a security fence would be installed around the entire perimeter of each site.

Construction activities and the storage of construction materials would be confined to each pump station site. Figures 2.2.3-1 and 2.2.3-2 are plot plans for typical pump stations.

2.3.4.2 Tank Farm Construction

The tank farm would be installed on a 74-acre site that would also include pump station 32. Wildhorse Creek extends through the site, but there would not be any construction activities in the creeks or on its banks. Portions of the site to be developed would be cleared and graded to create a level work surface for the tanks. The 350,000-barrel tanks would be welded steel tanks with external floating roofs that would be installed inside an impervious bermed area that would act as secondary containment. The piping in the tank farm area would be both above and below ground. The tanks and associated piping would be isolated electrically from the pipeline and protected by a separate cathodic protection system. The tank farm would use the electrical supply and control system of the adjacent pump station (see Figure 2.2.6-1). The tank farm would be final graded and a permanent security fence would be installed around the entire perimeter of the 74-acre site.

After successful hydrostatic testing of the tanks and associated piping and manifolds, the control system would be put into service and the tanks would be connected to the pipeline via the manifold. Each tank would have a separate water screen and fire suppression system supplied by an on-site fire water supply pond. A separate larger pond would be installed to manage storm water and mitigate any potential contamination from the site.

2.3.4.3 Mainline Valves and Delivery Sites

MLV construction would occur during mainline pipeline construction. All MLVs would be within the permanent ROW. To facilitate year-round access, the MLVs would be located as near as practicable to existing public roads. The construction sequence would consist of clearing and grading followed by trenching, valve installation, fencing, cleanup, and site restoration. If necessary, new access roads would be constructed into the fenced MLV sites. Two 10,417-barrel surge relief tanks would be installed at the end of the Gulf Coast Segment in Nederland on at a previously disturbed site with an industrial property. The area would be graded as necessary for installation of the tank foundations, and the tanks would be installed inside a bermed, impervious area that would act as secondary containment.

2.3.5 Construction Schedule, Workforce and Environmental Inspection

2.3.5.1 Schedule and Workforce

Construction of the proposed Project would begin as soon as Keystone obtains all necessary permits, approvals, and authorizations. Based on the current permitting schedule, the proposed Project is planned to be placed into service in 2013, with the actual date dependant on dates of receipt of all necessary permits, approvals, and authorizations.

As currently planned, the proposed Project would be constructed using 17 spreads (see Table 2.3.5-1), with 10 spreads used for the Steele City Segment, 6 spreads for the Gulf Coast Segment, and 1 spread for the Houston Lateral. The construction schedule may affect the final spread configuration which may result in the need for additional but shorter spreads. In any construction year, all spreads within the same segment would be constructed simultaneously.

TABLE 2.3.5-1 Pipeline Construction Spreads Associated with the Proposed Project			
Spread Number	Location by Milepost (MP)^a	Approximate Length of Construction Spread (miles)	Bases for Construction^b
Steele City Segment			
Spread 1	MP 0 to 64	64	Hinsdale, Montana, and Glasgow, Montana
Spread 2	MP 64 to 164	100	Glasgow, Montana, and Circle, Montana
Spread 3	MP 164 to 273	109	Glendive, Montana, and Baker, Montana
Spread 4	MP 273 to 345	72	Buffalo, South Dakota
Spread 5	MP 345 to 448	104	Faith, South Dakota, and Union Center, South Dakota
Spread 6	MP 448 to 513	65	Phillip, South Dakota
Spread 7	MP 513 to 616	103	Murdo, South Dakota, and Winner, South Dakota
Spread 8	MP 616 to 679	63	Fairfax, Nebraska, Stuart, Nebraska, and O'Neill, Nebraska
Spread 9	MP 679 to 789	109	Greeley, Nebraska, and Central City, Nebraska
Spread 10	MP 789 to 852	63	York, Nebraska, Beatrice, Nebraska, and Fairbury, Nebraska
Gulf Coast Segment			
Spread 1	MP 0 to 95	95	Holdenville, Oklahoma
Spread 2	MP 95 to 185	90	Paris, Texas
Spread 3	MP 185 to 285	100	Mt. Pleasant, Texas
Spread 4	MP 285 to 371	86	Henderson, Texas, Nacogdoches, Texas, Crockett, Texas, Jacksonville, Texas
Spread 5	MP 371 to 435	64	Lufkin, Texas

TABLE 2.3.5-1 Pipeline Construction Spreads Associated with the Proposed Project			
Spread Number	Location by Milepost (MP)^a	Approximate Length of Construction Spread (miles)	Bases for Construction^b
Spread 6	MP 435 to 484	49	Sour Lake, Texas
Houston Lateral			
Spread 7	MP 0 to 49	49	Sour Lake, Texas, Liberty, Texas, Dayton, Texas

^a Mileposting for each segment of the proposed Project starts at 0.0 at the northernmost point of the segment and increases in the direction of oil flow.

^b Spreads 1 to 8 may use construction camps for construction bases.

Cross-country pipeline construction would typically proceed at a pace of approximately 20 constructed miles per calendar month per spread. Construction would occur in the following approximate sequence:

- 2 to 3 weeks (14 to 21 calendar days) of work on the ROW prior to the start of production welding. Activities would include clearing, grading, stringing, and ditching.
- Production welding at an average rate of 1.25 miles of pipe welded per working day over a 6-day work week (over 7 calendar days), resulting in completion of an average of about 7.5 miles of pipeline per week.
- 7 weeks (49 calendar days) of additional work after completion of production welding. Activities would include nondestructive testing, field joint coating, pipe installation, tie-ins, backfill, ROW clean-up, hydrostatic testing, reseeding, and other ROW reclamation work.

Those time periods and rates of progress were used as the basis for determining the duration of construction activities on the ROW presented in Table 2.3.5-2 for various spread lengths. Construction in areas with greater congestion or higher population, in industrial areas, or in areas requiring other special construction procedures could result in a slower rate of progress.

TABLE 2.3.5-2 Cross-Country Construction Times Based on Estimates of Schedule				
Spread Length	Pre-welding	Welding Time	Post-welding and Clean-up	Total Duration
80 miles	21 days	75 days	49 days	145 days (21 weeks)
90 miles	21 days	84 days	49 days	154 days (22 weeks)
100 miles	21 days	94 days	49 days	164 days (24 weeks)
120 miles	21 days	112 days	49 days	182 days (26 weeks)

In addition, approximately 1 month would be required for contractor mobilization before the work is started and 1 month would be required for contractor demobilization after the work is finished. In general 500 to 600 construction and inspection personnel would be required for each spread, except for the Houston Lateral, which would require approximately 250 workers. Each spread would require about 6 to 9 months to complete, including mobilization and demobilization.

Tank farm construction would involve approximately 30 to 40 construction personnel over a period of 15 to 18 months concurrent with mainline construction. Construction of new pump stations would require 20 to 30 additional workers at each site. Construction of all pump stations would be completed in 18 to 24 months.

A peak workforce of approximately 5,000 to 6,000 personnel would be required to construct the entire Project and would be spread along the nearly 1,384-mile-long route. All workers would be trained and certified for their specific field of work (e.g., welders would be qualified as required by 49 CFR 195.222 and the Project-specific PHMSA special condition 18). Construction personnel would consist of Keystone employees, contractor employees, construction inspection staff and environmental inspection staff. Keystone would attempt to hire construction staff from the local population through its construction contractors and subcontractors. Assuming that qualified personnel are available, approximately 10 to 15 percent (50 to 100 people per spread) could be hired from the local work force for each spread, although this may not be possible in rural areas.

2.3.5.2 Environmental Inspection

Keystone would use Environmental Inspectors on each construction spread. The Environmental Inspectors would review the Project activities daily for compliance with state, federal, and local regulatory requirements and would have the authority to stop specific tasks as approved by the Chief Inspector. The inspectors would also be able to order corrective action in the event that construction activities violate the provisions of the CMR Plan, landowner requirements, or any applicable permit requirements.

2.4 OPERATIONS AND MAINTENANCE

The proposed Project would be operated, maintained, monitored, and inspected in accordance with 49 CFR 194 and 195 and other applicable federal and state regulations. In addition to the requirements of 49 CFR 195, Keystone has agreed to incorporate 57 PHMSA Project-specific special conditions that address proposed Project operation, inspection, and monitoring (see Appendix U). The operational requirements of 49 CFR 195 and the PHMSA Project-specific Special Conditions related to operation of the proposed Project (Appendix U) would be included in the proposed Project operations, maintenance, and emergencies manual that would be required by 49 CFR 195.402, and they would also be incorporated into Keystone's existing Operations Control Center (OCC) in Calgary, Canada.

The remainder of this section addresses normal operation and routine maintenance (Section 2.4.1) and abnormal operations (Section 2.4.2).

2.4.1 Normal Operations and Routine Maintenance

Keystone would prepare the manuals and written procedures for conducting normal operations, maintenance, inspection, and monitoring activities as required by the PHMSA regulations, particularly as required by 49 CFR 195.402 and in the applicable PHMSA Project-specific special conditions (see Appendix U). This would include development and implementation of an annual Pipeline Maintenance Program (PMP) to ensure the integrity of the pipeline. The PMP would include valve maintenance, periodic inline inspections, and cathodic protection readings to ensure facilities are reliable and in service. Data collected in each year of the program would be fed back into the decision-making process for the development of the following year's program.

The Project OCC would be manned by experienced and highly trained personnel 24 hours per day, every day of the year in Calgary. In addition, a fully redundant backup OCC would be constructed, operated,

and maintained, also in Canada. Primary and backup communications systems would provide real-time information from the pump stations to field personnel. The control center would have highly sophisticated pipeline monitoring systems including a leak detection system capable of identifying abnormal conditions and initiating visual and audible alarms. Automatic shut down systems would be initiated if a valve starts to shut and all pumps upstream would turn off automatically. All other pipeline situations would require human response.

The proposed Project would include a supervisory control and data acquisition (SCADA) system to constantly monitor the pipeline system. The SCADA system would be installed and operated in accordance with the requirements of 49 CFR 195 and PHMSA Project-specific special conditions 24 through 31 (see Appendix U). SCADA facilities would be located in the OCC and along the pipeline system, and all pump stations and delivery facilities would have communication software that sends data back to the OCC. The pipeline SCADA system would allow the OCC to remotely read intermediate MLV positions, tank levels, and delivery flow and total volume. The OCC personnel would also be able to start and stop pump stations and open and close MLVs. SCADA systems are further discussed in Sections 2.4.2.1 and 3.13.4.5.

The pipeline ROW would be inspected via aerial and ground surveillance to provide prompt identification of possible encroachments or nearby construction activities, ROW erosion, exposed pipe, or any other conditions that could result in damage to the pipeline. The aerial surveillance of the pipeline ROW would be carried out at least 26 times per year at intervals not to exceed 3 weeks as required by 49 CFR 195.412. Landowners would be encouraged to report any pipeline integrity concerns to Keystone or to PHMSA. Intermediate MLVs and MLVs at pump stations would also be inspected. As required by 49 CFR 195.420(b), they would be inspected at intervals not to exceed 7.5 months but at least twice each calendar year.

In comments on the supplemental draft EIS, EPA expressed concern that relying solely on pressure drops and aerial surveys to detect leaks may result in smaller leaks going undetected for some time, resulting in potentially large spill volumes. In light of those concerns, EPA requested consideration of additional measures to reduce the risks of undetected leaks. A PHMSA report (2007) addressed the state of leak detection technology and its applicability to pipeline leak detection. External leak detection technology addressed included liquid sensing cables, fiber optic cables, vapor sensing, and acoustic emissions. In that report PHMSA concludes that while external leak detection systems have proven results for underground storage tank systems there are limitations to their applicability to pipeline systems and they are better suited to shorter pipeline segments. Their performance even in limited application is affected by soil conditions, depth to water table, sensor spacing, and leak rate. While it is acknowledged that some external detection methods are more sensitive to small leaks than the SCADA computational approach, the stability and robustness of the systems are highly variable and the costs are extremely high. Therefore, long-term reliability is not assured and the efficacy of these systems for a 1,384-mile long pipeline is questionable. It may be possible, however, to incorporate external leak detection methods along discrete segments of pipeline where particularly sensitive resources may exist. For example, in the development of the original Keystone pipeline, specific analysis was commissioned at the request of the North Dakota Public Utilities Commission to examine the possibility of using external leak detection in the area of the Fordville aquifer. That analysis was performed by Accufacts, Inc., a widely recognized expert on pipeline safety that has authored a report for the Pipeline Safety Trust on leak detection technology. The Accufacts, Inc. report (2007) on the Fordville aquifer noted:

“Such real-time external systems should be considered as complementing CPM [computational pipeline monitoring] leak detection in those few ultra-sensitive areas where the environment can quickly spread low rate releases. These systems may be justified in a few areas that can have

high consequences because of the number of sensitive receptors (i.e., people) or the potential to critically impact the environment.”

The author of the report defined “ultra-sensitive” areas as those areas where low rate or seepage pipeline release could “reach a sensitive area, have serious consequences, and could not be actively remediated.” (Accufacts, Inc. 2007).

DOS in consultation with PHMSA and EPA determined that Keystone should commission an engineering analysis by an independent consultant that would review the proposed Project risk assessment and proposed valve placement. The engineering analysis would, at a minimum, assess the advisability of additional valves and/or the deployment of external leak detection systems in areas of particularly sensitive environmental resources. The scope of the analysis and the selection of the independent consultant would be approved by DOS in consultation with PHMSA and EPA. After completion and review of the engineering analysis, DOS with concurrence from PHMSA and EPA would determine the need for any additional mitigation measures.

Relative to additional ground patrols, Keystone responded to a data request from DOS concerning the feasibility of more ground-level inspections. Keystone responded that based on land owner concerns, additional ground-level inspections are not feasible due to potential disruption of normal land use activities (e.g., farming, animal grazing). PHMSA technical staff indicated that such concerns about landowner acceptance of more frequent ground-level inspections were consistent with their experience with managing pipelines in the region. Although widespread use of ground-level inspections may not be warranted, in the start-up year it is not uncommon for pipelines to experience a higher frequency of spills from valves, fittings, and seals. Such incidences are often related to improper installation, or defects in materials. In light of this fact, DOS in consultation with PHMSA and EPA determined that if the proposed Project were permitted, it would be advisable for the applicant to conduct inspections of all intermediate valves, and unmanned pump stations during the first year of operation to facilitate identification of small leaks or potential failures in fittings and seals. In the normal course of maintenance beyond the first year of operation, Keystone would have crews at various places along the proposed Project corridor (e.g., maintenance inspections of cathodic protection system rectifiers, MLVs, and pump stations). These crews would be trained and experienced in the identification of crude oil releases. It should be noted that the 14 leaks from fittings and seals that have occurred to date on the existing Keystone Oil Pipeline were identified from the SCADA leak detection system and landowner reports.

PHMSA regulations at 49 CFR 195.450 and Special Condition 14 require that pipeline operators identify areas along the proposed pipeline corridor that would be considered High Consequence Areas (HCAs). While some of these areas need to be defined through sophisticated risk modeling, in general they are specific locales where an accidental release from a hazardous liquid pipeline could produce significant adverse consequences as described in 49 CFR 195.450. HCAs include navigable waterways, high population areas, and unusually sensitive areas. Keystone would need to identify the HCAs along the proposed route. Population changes along the route would be monitored throughout pipeline operation and any additional HCAs identified as necessary. Keystone would conduct a pipeline integrity management program in HCAs as required by 49 CFR 195.452 (Pipeline Integrity Management in High Consequence Areas).

All maintenance work would be performed in accordance with PHMSA requirements, the applicable PHMSA Special Conditions, and the stipulations in environmental permits issued for the proposed Project. Woody vegetation along the permanent easement would be cleared periodically in order to maintain accessibility for pipeline integrity surveys. Mechanical mowing or cutting would be carried out from time to time as needed along the permanent easement for normal vegetation maintenance.

Cultivated crops would be allowed to grow in the permanent easement, but trees would be removed from the permanent ROW in all areas. In areas constructed using the HDD method, trees would be cleared as required on a site specific basis.

Permanent erosion control devices would be monitored to identify any areas requiring repair. The remainder of the ROW would be monitored to identify areas where additional erosion control devices would be necessary to prevent future degradation. The ROW would be monitored to identify any areas where soil productivity has been degraded as a result of pipeline construction. In these areas, reclamation measures would be implemented to rectify the problems.

Operation and maintenance of the pipeline system would typically be accomplished by Keystone personnel. The permanent operational pipeline workforce would comprise about 20 U.S. employees strategically located along the length of the pipeline in the U.S.

2.4.2 Abnormal Operations

Keystone would implement Abnormal Operating Procedures in accordance with 49 CFR Section 195.402(d). Those procedures would be developed and documented in a manual as required by 49 CFR 195.402. The manual would include procedures to provide safety when operating design limits have been exceeded. That would include investigating and correcting the cause of unintended closure of valves or shutdowns, increases or decreases in pressure or flow rate outside normal operating limits, loss of communications, operation of any safety device, and any other malfunction of a component, deviation from normal operation, or personnel error which could cause a hazard to persons or property. Procedures would also include checking variations from normal operation after abnormal operation has ended at sufficient critical locations in the system to accomplish the following:

- Assure continued integrity and safe operation;
- Identify variations from normal operation of pressure and flow equipment and controls;
- Notify responsible operator personnel when notice of an abnormal operation is received;
- Review periodically the response of operator personnel to determine the effectiveness of the procedures controlling abnormal operation; and
- Take corrective action where deficiencies are found.

The operations manager on duty would be responsible for executing abnormal operating procedures in the event of any unusual situation.

2.4.2.1 Pipeline Integrity, SCADA, and Leak Detection

The following overlapping and redundant integrity systems and measures would be incorporated into the proposed Project:

- Quality Assurance (QA) program for pipe manufacture and pipe coating;
- FBE coating;
- Cathodic protection;
- Non-destructive testing of 100 percent of the girth welds;
- Hydrostatic testing;
- Periodic internal cleaning and high-resolution in-line inspection;

- Depth of cover exceeding federal standards;
- Periodic aerial surveillance;
- Public awareness program;
- SCADA system; and
- An OCC with complete redundant backup, providing monitoring of the pipeline every 5 seconds, 24 hours per day, every day of the year.

SCADA facilities would be used to remotely monitor and control the pipeline system. This would include a redundant fully functional backup system available for service at all times. Automatic features would be installed as integral components within the SCADA system to ensure operation within prescribed pressure limits. Additional automatic features would be installed at the local pump station level and would provide pipeline pressure protection in the event communications with the SCADA host are interrupted.

Software associated with the SCADA monitoring system and volumetric balancing would be used to assist in leak detection during pipeline operations. If pressure indications change, the pipeline controller would immediately evaluate the situation. If a leak is suspected, the ERP would be initiated, as described in Section 2.4.2.2. If there is a pipeline segment shutdown due to a suspected leak, operation of the affected segment would not be resumed until the cause of the alarm (e.g., false alarm by instrumentation or a leak) is identified and repaired. In the case of a reportable leak, OHMSA approval would be required to resume operation of the affected segment.

A number of complementary leak detection methods and systems would be available within the OCC and would be linked to the SCADA system. Remote monitoring would consist primarily of monitoring pressure and flow data received from pump stations and valve sites that would be fed back to the OCC by the SCADA system. Software based volume balance systems would monitor receipt and delivery volumes and would detect leaks down to approximately 5 percent of pipeline flow rate. Computational Pipeline Monitoring or model-based leak detection systems would separate the pipeline system into smaller segments and would monitor each segment on a mass balance basis. These systems would detect leaks down to a level of approximately 1.5 to 2 percent of the pipeline flow rate. Computer-based, non-real time, accumulated gain/loss volume trending would assist in identifying low rate or seepage releases below the 1.5 to 2 percent by volume detection thresholds. If any of the software-based leak detection methods indicates that a predetermined loss threshold has been exceeded, an alarm would be sent through SCADA and the Controller would take corrective action. The SCADA system would continuously poll all data on the pipeline at an interval of approximately 5 seconds

If an accidental release were to occur, the operator would shut down operating pumping units and close the isolation valves. Once shutdown activities are initiated, it would take approximately 9 minutes to complete the emergency shut-down procedure (shut down operating pumping units) and an additional 3 minutes to close the isolation valves.

In addition to the SCADA and complimentary leak detection systems, direct observation methods, including aerial patrols, ground patrols and public and landowner awareness programs, would be implemented to encourage and facilitate the reporting of suspected leaks and events that could suggest a threat to the integrity of the pipeline.

Several commenters suggested that external mechanical leak detection systems should be considered. In response, DOS requested information from Keystone regarding the feasibility of installing mechanical external leak detection systems along the proposed Project corridor. Keystone considers that the presently

available technology for external leak detection is not practicable for use along a 1,384 mile pipeline. Additionally, a PHMSA report (2007) addressed the state of leak detection technology and its applicability to pipeline leak detection. External leak detection technology addressed included liquid sensing cables, fiber optic cables, vapor sensing, and acoustic emissions. In that report PHMSA concludes that while external leak detection systems have proven results for underground storage tank systems there are limitations to their applicability to pipeline systems and they are better suited to shorter pipeline segments. Their performance even in limited application is affected by soil conditions, depth to water table, sensor spacing, and leak rate. While it is acknowledged that some external detection methods are more sensitive to small leaks than the SCADA computational approach, the costs are extremely high and the stability and robustness of the systems are highly variable. Therefore, long-term reliability is not assured and the efficacy of these systems for a 1,384-mile long pipeline is questionable.

2.4.2.2 Emergency Response Procedures

There were many comments on the draft EIS concerning the ERP, including suggestions that a supplemental draft EIS be issued to include a more complete ERP and allow for public review of that plan. Those issues are addressed below along with additional information on the proposed Project ERP. Section 3.13.1.1 provides additional information on the regulations associated with an ERP.

PHMSA requires that pipeline operators prepare and abide by more than one written emergency plan for responding to emergencies on their systems.

First, 49 CFR 194, which resulted from the CWA as amended by the Oil Pollution Act of 1990 (OPA 90) and as implemented by Executive Order 12777, requires that pipeline operators have response plans that ensure resources are available to remove, mitigate, or prevent a discharge from an oil pipeline that could cause substantial or significant harm to the environment, including a worst case discharge. As stated in 49 CFR 194.7(a), a pipeline operator “may not handle, store, or transport oil unless the operator has submitted a response plan meeting requirements of this part,” and as stated in 49 CFR 194.7(b), operators must also operate onshore pipeline facilities in accordance with the approved response plan. In addition, 49 CFR 194.107 requires that the response plan include “procedures and a list of resources for responding, to the maximum extent practicable, to a worst case discharge, and to a substantial threat of such a discharge.” Keystone would submit a Pipeline Spill Response Plan (PSRP) to PHMSA prior to the initiation of proposed Project operations in accordance with the requirements of 49 CFR 194. The PSRP would describe how spills would be responded to in the event of a release from the proposed Project resulting from any cause (e.g., corrosion, third-party damage, natural hazards, materials defects, hydraulic surge). The plan would address the maximum spill scenario and the procedures that would be in place to deal with the maximum spill. The PSRP requires PHMSA review and approval; however, there is a 2-year grace period under which operations can proceed, thus allowing PHMSA time to review the document in light of as-built Project conditions and to require incorporation of any needed changes to ensure system safety prior to PHMSA approval.

As required by 49 CFR 195.40, Keystone would also prepare and follow a manual of written procedures for conducting normal operations and maintenance activities and handling abnormal operations and emergencies. This manual would be reviewed by PHMSA at intervals not exceeding 15 months, but at least once each calendar year, and appropriate changes would be made as necessary to ensure that the manual is effective. This manual would be prepared before initial operations of the proposed Project and appropriate sections would be kept at locations where operations and maintenance activities are conducted. The emergency section of this operations and maintenance plan would be prepared by Keystone in a separate document that Keystone refers to as the Emergency Response Plan (ERP).

While EPA has authority under the CWA and OPA 90 with respect to regulation of onshore non-transportation related facilities and EPA requires the development and submittal of a Facility Response Plan (FRP) for any such facility, it appears that none of the facilities or activities associated with the proposed Project would be non-transportation-related equipment or activities subject to the EPA regulatory authority, as previously noted in Section 2.3.

Keystone would therefore be required to develop a PSRP for review and approval by PHMSA and an ERP for review by PHMSA for the proposed Project. PHMSA may request EPA and U.S. Coast Guard consultation on the response elements of the PSRP. Keystone would share on its own volition portions of the PSRP with community emergency responders along the proposed pipeline corridor to ensure an appropriate level of collaborative emergency response planning. However, based on a PHMSA advisory bulletin issued on November 3, 2010, Keystone would be required to share the ERP with local emergency responders in relevant jurisdictions along the proposed Project corridor.

While the draft PSRP and the draft ERP for the proposed Project are not yet available, Keystone prepared similar plans for the existing Keystone Oil Pipeline Project. These plans for the proposed Project would have the same general approach as those plans but would have many specific differences, such as the names and contact information for responders along the proposed Project route. The publically available portion of the Keystone Oil Pipeline System ERP is included as Appendix C to the EIS (some of the ERP and the PSRP are considered confidential by PHMSA and the U.S. Department of Homeland Security). As described in Section 3.13.1.1, the existing Keystone Oil Pipeline Project documents would be used as templates for the plans for the proposed Project. Project-specific information would be inserted into the plans as it becomes available. In addition, response equipment would be procured and strategically positioned along the route, staff would be trained in spill response and the Incident Command System, and emergency services and public officials would be educated on all aspects of the proposed Project and what their roles would be if an accidental release were to occur. If a release were to occur, Keystone and its contractors would be responsible for recovery and cleanup. PHMSA would require a certification from Keystone that necessary emergency response equipment is available in the event of an unplanned spill prior to providing Keystone with an authorization to begin operating the proposed Project.

The specific locations of Keystone's emergency responders and equipment would be determined upon conclusion of the pipeline detailed design and described in the PSRP and ERP. Company emergency responders would be placed consistent with industry practice and with applicable regulations, including 49 CFR Parts 194 and 195. The response time to transfer additional resources to a potential leak site would follow an escalating tier system, with initial emergency responders capable of reaching all locations within 6 hours in the event of a spill. Typically, emergency responders would be based in closer proximity to the following areas:

- Commercially navigable waterways and other water crossings;
- Populated and urbanized areas; and
- Unusually sensitive areas, including drinking water locations, ecological, historical, and archaeological resources.

Types of emergency response equipment situated along the pipeline route would include pick-up trucks, one-ton trucks and vans; vacuum trucks; work and safety boats; containment boom; skimmers; pumps, hoses, fittings and valves; generators and extension cords; air compressors; floodlights; communications equipment including cell phones, two way radios and satellite phones; containment tanks and rubber bladders; expendable supplies including absorbent booms and pads; assorted hand and power tools including shovels, manure forks, sledge hammers, rakes, hand saws, wire cutters, cable cutters, bolt cutters, pliers and chain saws; ropes, chains, screw anchors, clevis pins and other boom connection

devices; personnel protective equipment (PPE) including rubber gloves, chest and hip waders and airborne contaminant detection equipment; and wind socks, signage, air horns, flashlights, megaphones and fluorescent safety vests. Emergency response equipment would be maintained and tested in accordance with manufacturers recommendations.

Additional equipment including helicopters, fixed wing aircraft, all-terrain vehicles, snowmobiles, backhoes, dump trucks, watercraft, bull dozers, and front-end loaders could also be accessed depending upon site-specific circumstances. Other types, numbers and locations of equipment would be determined upon conclusion of the pipeline detailed design and the completion of the PSRP and the ERP for the proposed Project.

Several federal regulations define the notification requirements and response actions in the case of an accidental release, including the National Oil and Hazardous Substances Pollution Contingency Plan (40 CFR Part 300), the CWA, and OPA 90.

If an accidental release occurs, Keystone would implement several procedures to mitigate damage, including a line shut down. Other procedures would include immediate dispatch of a first responder to verify the release and secure the site. Simultaneously, an Incident Command System would be implemented and internal and external notifications would take place. The National Response Center (NRC) would be notified if the release meets one of the prescribed criteria. Keystone and the NRC would also notify other regional and local emergency response agencies as quickly as possible. All of this information would be included in the ERP for the proposed Project.

Many commenters expressed concern that an accidental release of heavy crude oil from the proposed Project would require unique methods to clean up the oil. As described in Section 3.13.5.3, heavy WCSB crude oil is similar to heavy crude oil currently being processed in refineries in the Houston area and elsewhere in the U.S. Therefore, the methods used to cleanup crude oil accidentally released from the proposed Project would be similar to methods used elsewhere in the U.S. to address a heavy crude oil release.

Some commenters also suggested that the EIS should provide alternatives to the ERP and evaluate those alternatives as a part of the NEPA environmental review process. Keystone's ERP would be prepared to meet the PHMSA requirements in 49 CFR 195.40 and would reflect actual field conditions. Additionally, Keystone's PSRP would be prepared to meet the requirements of 49 CFR 194. Due to the range of possible accidental release scenarios (including timing, size, location, season, weather conditions, and many other variables), it is not possible to assess the impact of each and every response and cleanup scenario. As a result, NEPA environmental reviews do not assess the relative effectiveness of specific procedures and PSRP and ERP alternatives.

In the event of a suspected release or if a release is reported to the OCC, after verification there would be an emergency pipeline shutdown. This would involve stopping all operating pumping units at all pump stations. The on-call response designate would respond to and verify an incident. Once the OCC notifies the individual and an assessment of the probability and risk is established, field personnel could elect to dispatch other resources as soon as practical. Response efforts would first be directed to preventing or limiting any further contamination of the waterway, once any concerns with respect to health and safety of the responders have been addressed.

Many commenters expressed concern about abnormal pipeline operations that could result in an explosion. A review of PHMSA data related to pipeline accidents indicates that most "petroleum or hydrocarbon pipeline explosions" occur in pipelines that are transporting highly flammable, highly volatile hydrocarbons such as natural gas, liquid propane gas (LPG), propane, gasoline, naphtha, or

similar products. Typically, any of those materials accidentally released from the pipeline form a flammable vapor cloud that can explode when it reaches a certain concentration level in air, particularly in a confined space. In rare cases diesel, gas condensate, kerosene, or similarly-refined liquid hydrocarbon ignite and burn explosively if the vapors are exposed to a fire or similar high temperature heat source, usually a fire caused by some other accident.

As noted in Section 3.13, PHMSA data for onshore oil and hazardous material pipelines indicate that only 6 of 2,706 (0.2 percent) of incidents that occurred from 1990 through 2009 were attributed to “fire/explosion as a primary cause.” A search of the internet for reports of crude oil pipeline explosions suggests that (1) there are very few if any explosions in crude oil pipeline operation that were the result of a failure of the pipeline as a primary cause, and (2) the very few that have occurred are attributable to explosions in ancillary facilities or errors in operations unassociated with crude oil transportation. For example, the recent explosion and fire in the crude oil pipeline/storage tank area in Dalian, China occurred as a result of an improper desulfurization operation; the primary cause was not the transport of crude oil in the pipeline.

The proposed Project would use pump stations that are powered by electricity; as a result, there would not be natural gas or other petroleum products at the facility that could ignite explosively. An accidental crude oil spill from the pipeline or at a pump station would likely result in some hydrocarbon vapors, but they would not be in confined spaces and therefore would be unlikely to explode.

A fire associated with a release from a crude oil pipeline is relatively rare. In the event of a fire, local emergency responders would execute the roles listed above and more specifically in the PSRP and the ERP, and firefighters would take actions to prevent the crude oil fire from spreading to residential areas.

2.4.2.3 Remediation

Corrective remedial actions would be dictated by federal, state, and local regulations and enforced by the USEPA, OPS, and appropriate state and/or local agencies. Required remedial actions may be large or small, dependent upon a number of factors including state-mandated remedial cleanup levels, potential effects to sensitive receptors, the volume and extent of the contamination, whether or not there is a violation of water quality standards, and the magnitude of adverse impacts caused by remedial activities. A large remediation action may include the excavation and removal of contaminated soil, for example, or could involve allowing the contaminated soil to recover through natural attenuation or environmental fate processes such as evaporation and biodegradation. Additional information on remediation is presented in Section 3.13 (Reliability and Safety).

If there is an accidental release from the proposed Project, Keystone would implement the remedial measures necessary to meet the federal, state, and local standards that are designed to ensure protection of human health and environmental quality.

2.5 CONNECTED ACTIONS

DOS identified four actions that are separate from the proposed Project that are not part of the Presidential Permit application submitted by Keystone and has determined that they are connected actions for the purposes of this NEPA review as defined by 40 CFR 1508.25(a)1. The four connected actions are described in the following subsections:

- Electrical distribution lines and substations associated with the proposed pump stations (Section 2.5.1);
- The Big Bend to Witten 230-kilovolt (kV) electrical transmission line (Section 2.5.2);

- The Bakken Marketlink Project (Section 2.5.3); and
- The Cushing Marketlink Project (Section 2.5.4).

Preliminary information on the design, construction, and operation of these projects is presented below. Although the permit applications for these projects would be reviewed and acted on by other agencies, the potential impacts of these projects have been analyzed in the EIS based on currently available information and are addressed within each resource assessed in Section 3.0. However, in some cases only limited information was available on the design, construction, and operation of the projects. The reviews of permit applications by other agencies would include more detailed environmental reviews of the connected actions.

DOS is not aware of any planned refinery upgrades or new refinery construction that would directly result from implementation of the proposed Project.

2.5.1 Electrical Distribution Lines and Substations

2.5.1.1 Overview

Electrical power for the proposed Project would be obtained from local power providers. These power providers would construct the necessary substations and transformers and would either use existing service lines or construct new service lines to deliver electrical power to the specified point of use. The electrical power providers would be responsible for obtaining the necessary permits, approvals, or authorizations from federal, state, and local governments, except in those instances in Montana where new service lines less than 10 miles in length would be constructed. Under Montana regulations, these distribution lines would be considered “associated facilities” connected with the overall pipeline system. Where this occurs, the review and approval of the new lines would occur as part of the review and approval of Keystone’s MFSA application for a Certificate of Compliance.

New electrical transmission power lines with voltages of 69 kV or greater would be constructed to service the pump stations and the Cushing tank farm. Table 2.5.1-1 lists the electrical power supply requirements for the pump stations and Figures 2.1-1 through 2.1-6 depict the locations of the distribution lines.

TABLE 2.5.1-1 Electrical Power Supply Requirements for Pump Stations					
Pump Station No.	Milepost^a	Transformer Size (Megavolt Amperes)	Kilovolts of Electricity	Estimated Electrical Line Length (miles)	Power Provider
Steele City Segment					
Montana					
PS-09	1.2	20/27/33	115	61.8 ^b	Big Flat Electric Cooperative
PS-10	49.5	20/27/33	115	49.1 ^c	NorVal Electric Cooperative
PS-11	98.4	20/27/33	230	0.2	Norval Electric Cooperative
PS-12	149.1	20/27/33	115	3.2	McCone Electric Cooperative
PS-13	199.6	20/27/33	115	15.2	Tongue River Electric Cooperative
PS-14	237.1	20/27/33	115	6.3	Montana-Dakota Utilities Company
South Dakota					
PS-15	285.7	20/27/33	115	24.5	Grand Electric Cooperative

**TABLE 2.5.1-1
Electrical Power Supply Requirements for Pump Stations**

Pump Station No.	Milepost^a	Transformer Size (Megavolt Amperes)	Kilovolts of Electricity	Estimated Electrical Line Length (miles)	Power Provider
PS-16	333.7	20/27/33	115	40.1	Grand Electric Cooperative
PS-17	387.4	20/27/33	115	10.9	Grand Electric Cooperative
PS-18	440.2	20/27/33	115	25.9	West Central Electric Cooperative
PS-19	496.1	20/27/33	115	20.4	West Central Electric Cooperative
PS-20	546.7	20/27/33	115	17.2	Rosebud Electric Cooperative
PS-21	591.9	20/27/33	115	20.1	Rosebud Electric Cooperative
Nebraska					
PS-22	642.4	20/27/33	115	24.0	Niobrara Valley Electric
PS-23	694.5	20/27/33	115	36.0	Loup Valleys Rural PPD
PS-24	751.7	20/27/33	115	9.0	Southern Power District
PS-25	800.5	20/27/33	69	0.1	Perennial PPD
PS-26	851.3	20/27/33	115	0.5	Norris PPD
Keystone Cushing Extension					
Kansas					
PS-27	49.0*	20/27/33	115	4.6	Clay Center Public Utility
PS-29	144.5*	20/27/33	115	8.9	Westar Energy
Gulf Coast Segment					
Oklahoma					
PS-32	0.0	17/22/28	138	6.9	Oklahoma Gas and Electric Company
PS-33	49.0	20/27/33	138	0.3	Canadian Valley Electric Cooperative/PSO
PS-34	95.4	20/27/33	138	5.5	People's Electric Cooperative/PSO
PS-35	147.4	20/27/33	138	0.0	Southeastern Electric Cooperative
Texas					
PS-36	194.5	20/27/33	138	7.4	Lamar Electric Cooperative
PS-37	238.6	20/27/33	138	0.1	Wood County Electric Cooperative
PS-38	284.0	20/27/33	138	0.6	Cherokee County Electric Cooperative
PS-39	338.1	20/27/33	138	9.1	Cherokee County Electric Cooperative
PS-40	380.5	20/27/33	138	0.3	Sam Houston Electric Cooperative
PS-41	435.2	20/27/33	240	0.4	Sam Houston Electric Cooperative

^a Mileposting for each segment of the proposed Project start starts at 0.0 at the northernmost point of each segment and increases in the direction of oil flow.

^b Extends across approximately 32 miles of BLM land.

^c Extends across approximately 4.8 miles of BLM land.

Most of the proposed new electrical distribution lines to service pump stations would be 115-kV lines strung a single-pole and/or H-frame wood poles. The poles would typically be about 60 to 80 feet high with wire span distances of from about 250 to 400 feet.

Each pump station would have a substation integrated into the general pump station layout. In some cases (pump stations 36 and 41), Keystone would share pump station land with the local utility for the installation of their substation. Sharing of substation land at the pump station would allow the utility to provide a second transformer to provide service to the rural customers in the area.

The exact location of each substation cannot be identified at this time because the electrical supply lines would access pump stations from different alignments. Each substation footprint would be approximately 1 to 1.5 acres and is included in the total land size of each pump station. The actual size of a substation would be dictated by the specific design and size requirements of the local power supply company, the capacity of the power supply lines connected to each specific pump station, and the associated equipment. Figures 2.2.3-1 and 2.2.3-2 provide typical layouts for substations and pump stations.

Other electrical power requirements, such as power for MLVs, would be supplied from distribution service drops from adjacent distribution power lines with voltage below 69 kV. Each distribution service drop would typically be less than 200 feet long, and would require the installation of one or two poles and a transformer. The electric utility would typically install a pole-mounted transformer within 200 feet of the valve site location. However, in some cases the electric utility would install the transformer on an existing pole which would be more than 200 feet from the valve site. The decision on where the transformer pole would be located would generally be based on the most economical installation. For example, MLVs north of the Milk River in Montana would be supplied from transformers on poles along small lines that currently supply power to irrigation systems. Upon completion of the new service drops, the electrical power providers would restore the work area as required, in accordance with local permits.

Preliminary routing for new electrical distribution lines was established in consultation with each utility company. Where practicable, these preliminary routes were along existing county roads, section lines, or field edges, to minimize interference with adjacent agricultural lands. The routes are subject to change as pumping station supply requirements are further reviewed with power providers and in some cases, as a result of environmental review of the routes by the agencies with jurisdiction.

Electromagnetic induction can occur from power lines, which can cause noise, radio, and television interference. This potential interference would be mitigated by siting the power line away from residences (500 feet minimum, if possible) and by routing the power line to reduce parallel metallic interferences.

Power line Radio Frequency Interference (RFI) is usually caused by sparking (arcs) which is typically caused by loose hardware. The power provider design uses spring washers to keep hardware tight to minimize arcing and conductor supports use specialized clamps to keep the conductor and support clamps firmly connected to further reduce the potential for arcing. Defective lightning arrestors could also contribute to RFI. The power providers would use a static conductor at the top of the pole to mitigate lightning-caused flashovers. Lightning arrestors would be limited to the stations where major equipment is located.

The radio communication systems at the proposed Project facilities would operate on specific frequencies licensed by the Federal Communications Commission (FCC). This would reduce the risk of any interference with radio, television, or any other communication system in the area.

Several Montana residents expressed concern about the source of energy for the electricity provided by utility companies to power the pump stations and mainline valves in Montana. Some Montana residents also asked about the potential for residential rates to increase.

Electric cooperatives (coops) in Montana obtain electricity from a variety of sources, including coal-fired power plants, hydroelectric plants, and at wind farms in the area. Many coops have service agreements

with Western Area Power Administration (Western), Bonneville Power Administration (BPA), PPL Montana, and Basin Electric Power Cooperative, some of which likely results in electrical energy being transported to Montana from many distant and varied sources. This energy flows primarily across transmission owned by Western and NorthWestern Energy to delivery points within the cooperative systems. The energy is delivered to the members/consumers through distribution lines, substations, and other related infrastructure.

As a result, it is not possible to identify the specific facilities or the specific sources of energy that would be used to generate the electricity that would be used at the pump stations and mainline valves in Montana. Each of the coops involved has agreed to provide the necessary power and would likely request the additional power from their current providers. Any increase in power generation at the plants providing that power would have to be conducted in compliance with environmental regulations. If additional nonrenewable resources are needed to generate the additional, the provision of those resources would also have to be accomplished consistent with regulatory requirements.

2.5.1.2 Construction Procedures

All distribution lines and substations would be installed and operated by local power providers. This work would include ROW acquisition, ROW clearing, construction, site restoration, cleanup, and obtaining any necessary permits, approvals, or authorizations from federal, state, and local governments. The proposed distribution lines would require a 100-foot-wide construction ROW and an 80-foot-wide permanent ROW. Each power provider would develop detailed power line construction procedures to address site specific conditions. In general, construction of the electrical distribution lines would involve the following:

- **ROW Acquisition/Easements:** The electric power provider would obtain any necessary easements.
- **ROW Clearing:** Limited clearing would be required along existing roads in native and improved grasslands and croplands. Either tree trimming or tree removal would be conducted to provide adequate clearance between the conductors and underlying vegetation.
- **Power Line Construction:** Power line poles and associated structures would be delivered on flatbed trucks. Radial arm diggers would typically be used to excavate the required holes. Poles would be either wood or steel and would be directly embedded into the excavated holes using a mobile crane or picker truck where appropriate. Anchors may be required at angles and dead ends.
- **Stringing:** After the power line poles are in place, conductors (wires) would be strung between them. Pulling or reeling areas would be needed for installation of the conductor wires which would be attached to the poles using porcelain or fiberglass insulators.
- **Restoration:** After completion of distribution line construction, the disturbed areas would be restored. All litter and other remaining materials would be removed from the construction areas and disposed of in accordance with regulatory requirements. Preconstruction contours would be restored as closely as possible and reseeded would follow landowner requirements.

2.5.2 Big Bend to Witten 230-kV Transmission Line

2.5.2.1 Overview

After receipt of information on the power requirements for the proposed pump stations in South Dakota, the Western Area Power Administration (Western) conducted a joint system engineering study to determine system reliability under the proposed loads at full Project electrical energy consumption. The joint system engineering studies determined that a 230-kV transmission line originating at the Fort Thompson/Big Bend area and extending south to the existing Witten Substation would be required to

support voltage requirements for pump stations 20 and 21 in the Witten area when the proposed Project is operating at maximum capacity.

To address this requirement, Western proposes to convert the existing Big Bend-Fort Thompson No. 2, 230-kV transmission line turning structure, located on the south side of the dam, to a double-circuit structure. Western would then construct approximately 2.1 miles of new double-circuit transmission line south to a new substation, tentatively named Big Bend Substation, which would also be constructed by Western. The new switchyard/substation would be a 3-breaker ring bus configuration, expandable to a breaker and a half configuration. The new 2.1-mile-long double-circuit 230-kV transmission line would be owned, constructed, and operated by Western. After construction, the ownership of the Big Bend Substation would be transferred to the Basin Electric Power Cooperative (BEPC) which would then own and operate it. Western would complete design of the new substation and double-circuit transmission line in 2012 and would begin construction in the spring of 2013.

BEPC proposes to construct and operate a new 230-kV transmission line from the proposed new Big Bend Substation to the existing Witten Substation owned by Rosebud Electric Cooperative. The new Big Bend Substation and approximately 70-mile-long Big Bend to Witten 230-kV transmission line would assure future electric power requirements at pump stations 20 and 21 would be met without degrading system reliability when the proposed Project is operating at maximum capacity. The new Big Bend to Witten 230-kV transmission line would be built, owned, and operated by BEPC. The Witten Substation would also need to be expanded to accommodate the new switching equipment associated with the Big Bend to Witten 230-kV transmission line.

A SCADA system would interconnect the substations. Hardwire system communications would utilize fiber optics within the Optical Overhead Ground Wire between the substations. Microwave communications equipment would be installed for SCADA redundancy and to facilitate voice and data communications by field personnel. Additional communications facilities may also be needed. The proposed substation and transmission line projects would be in Lyman and Tripp counties in south-central South Dakota. The Big Bend Dam is in Lyman County, close to the city of Fort Thompson. The Witten Substation is in Tripp County near the city of Witten.

Western and BEPC identified two alternative corridors for the proposed Big Bend to Witten transmission line project, and there are nine route options within each corridor between the Big Bend and Witten substations. Initially, a 6-mile-wide corridor, Alternative Corridor A, was identified between an existing substation on the transmission grid and a proposed new substation at Big Bend. BEPC and Western then identified five preliminary alternative routes for the transmission line within Corridor A (see Figure 2.5.2-1); the five alternatives are the Western Alternative and Alternatives BEPC-A through BEPC-D. BEPC, Western, and the Lower Brule Reservation also identified Alternative Corridor B, which is also a 6-mile-wide corridor. This corridor follows a similar path from the existing Witten Substation to the proposed Big Bend Substation but with deviations in the southeast near Winner and the northeast near Reliance. Corridor B was further developed into four preliminary alternative routings for the transmission line (see Figure 2.5.2-1); the four alternatives are Alternatives BEPC-E through BEPC-H. The alternatives within both Corridor A and Corridor B cross the Lower Brule Reservation and connect with an existing transmission line near the Big Bend Dam.

BEPC is pursuing financing for the transmission line project from the Rural Utilities Service (RUS). Under the RUS regulations for implementation of NEPA, an Environmental Assessment (EA) must be prepared to assess potential environmental impacts of the proposed action. BEPC has indicated that RUS would serve as the lead agency for NEPA, and Western would serve as a cooperating agency. In early 2011, BEPC informed DOS that it would contract with an environmental consultant to prepare a Macro Corridor Study and an Alternative Evaluation Study prior to initiating scoping for the EA. Based on the

current schedule, BEPC anticipates that all project permits and approvals would be in place by the end of 2012, and construction could begin in early 2013, assuming that there would be a need for the transmission line at the end of the construction period.

2.5.2.2 Construction Procedures

The proposed transmission line would be constructed within a 125-foot-wide ROW. The specific structure type has not been determined, but would be either single- or two-pole structures.

All substation and switchyard work, including the placement of concrete foundations, erecting support structures, construction of control buildings, and the installation of electrical equipment would take place within secured areas. The proposed substation site at Big Bend and the expansion area at Witten would be cleared and leveled. Aggregate would be spread throughout undeveloped areas within the substation sites. Topsoil would be segregated from underlying soils and redistributed on disturbed areas outside the substation security fences. Soil erosion would be minimized during construction using BMPs. Substation components would be hauled to the site on local highways and roads and off-loaded using cranes and similar equipment. Concrete and aggregate from local sources would be hauled to the site by truck.

The impacts of construction and operation of the transmission line alternatives are generally addressed in Section 3.0 the EIS. However, DOS, Western, and the other cooperating agencies do not have sufficient design and construction information to establish an agency-preferred alternative for the proposed transmission line project. An additional and separate NEPA environmental review of the alternatives to the proposed transmission line will be conducted after the alternative routes are further defined. The design and environmental review of the proposed 230-kV transmission line are on a different schedule than the pipeline system itself. Regional transmission system reliability concerns are not associated with the initial operation of the proposed pipeline pump stations, but only for future operation at the maximum throughput volume of 830,000 bpd.

2.5.3 Bakken Marketlink Project

Keystone Marketlink, LLC (Keystone Marketlink), a wholly owned subsidiary of TransCanada Pipelines Limited, is proposing to construct and operate the Bakken Marketlink Project. That project would include construction of facilities to provide crude oil transportation service from near Baker, Montana to Cushing, Oklahoma via the proposed Project and from Cushing to delivery points at Nederland and Moore Junction (east of Houston), Texas, via the proposed Project. After a successful Open Season, Keystone Marketlink obtained commitments for transport of approximately 65,000 bpd of crude oil through the Bakken Marketlink Project. The project could deliver up to 100,000 bpd to the proposed Project depending on ultimate shipper commitments. Baker is near many existing and proposed crude oil gathering systems, pipelines, and crude oil storage tanks, and the Bakken Marketlink Project would provide direct access to PADD II and PADD III markets. The announced target in-service date for the Bakken Marketlink Project is the first quarter of 2013.

The project would consist of piping, booster pumps, meter manifolds and two tank terminals; one terminal would be near Plevna and Baker, Montana, and the second would be at the proposed Cushing tank farm. The Bakken Marketlink facilities would include two, 250,000-barrel tanks that would be used to accumulate crude from connecting third-party pipelines and terminals and a 100,000-barrel tank that would be use for operational purposes (see Figure 2.5.3-1). The facilities would also include a proposed 5 mile long pipeline that would initiate at an existing Montana tank farm facility in Township 7N Range 58E Section 4. The project is still in the preliminary stages of evaluating the options regarding the routing of this proposed pipeline.

The Bakken Marketlink Project facilities at the Cushing tank farm would include two, 250,000-barrel tanks that would be used for batch deliveries from the Baker facilities (see Figure 2.5.3-2). Figure 2.5.3-3 is a plot plan for the tank farm near Cushing that includes the Bakken Marketlink tanks, the Cushing Marketlink tanks, and two portions of the proposed Keystone XL Project (the Cushing tank farm and pump station 32).

Crude oil in the Bakken Marketlink storage tanks at the Cushing tank farm would either be pumped to the Keystone XL pipeline for delivery to PADD III or delivered to other pipelines and tank farms near Cushing. The Cushing tank farm would be near many pipelines, storage facilities, and refineries since Cushing is a major crude oil marketing, refining, and pipeline hub that provides shippers with many delivery options and market access. Delivery of the crude oil to Nederland would be as described in this EIS for the proposed Project.

The Bakken Marketlink Project would provide the first direct link between the prolific Bakken crude oil producing region and key U.S. markets near Cushing and the in the Gulf Coast area, which is the largest refining market in North America.

2.5.4 Cushing Marketlink Project

Keystone Marketlink also plans to construct and operate the Cushing Marketlink Project. The Cushing Marketlink Project would include construction and operation of facilities within the boundaries of the proposed Keystone XL Cushing tank farm. From there, crude oil would be transported by the proposed Keystone XL Project to delivery points at Nederland and Moore Junction (east of Houston), Texas. After a successful Open Season in late 2010, Keystone Marketlink obtained sufficient commitments to proceed with the project, which will have the ability to deliver approximately 150,000 barrels of crude oil per day to the proposed Keystone XI pipeline. On August 15, 2011, Keystone Marketlink initiated a second binding Open Season to obtain additional firm commitments from interested parties for the planned project.

The Cushing Marketlink facilities at the proposed Cushing tank farm site would be adjacent to the Cushing Oil Terminal, a key pipeline transportation and crude oil storage hub with over 50 million barrels of storage capacity. As a result, the Cushing Marketlink Project would be near many pipelines and storage facilities that could ship crude oil to the Cushing Marketlink facilities. The Cushing Marketlink Project is expected to alleviate current pipeline constraints from the Cushing area and provide shippers with a new transportation option from the Cushing market to the U.S. Gulf Coast. The announced target in-service date for the Cushing Marketlink Project is the first quarter of 2013.

The Cushing Marketlink Project would include construction and operation of receipt custody transfer metering systems and batch accumulation tankage consisting of two, 350,000 barrel tanks, with one tank dedicated for light sweet crude. The tanks would be located within the proposed Project's Cushing tank farm property, which also would house pump station 32 of the proposed Project (see Figure 2.5.3-3) and the storage tanks for the planned Bakken Marketlink storage tanks (described in Section 2.5.3). The tanks would accumulate batches from existing third-party pipelines and terminals for transportation to the U.S. Gulf Coast on the proposed Project. Delivery of the crude oil to delivery points in Texas would be as described in this EIS for the proposed Project.

2.6 FUTURE PLANS AND PROJECT DECOMMISSIONING

2.6.1 Future Plans

2.6.1.1 Proposed Project

As proposed, the Project would initially have a nominal transport capacity of approximately 700,000 bpd of crude oil. By increasing the capacity of the pump stations in the future, Keystone could transport up to 830,000 bpd of crude oil through the pipeline. Should Keystone decide to increase pumping capacity to 8300,000 bpd at a later date, the necessary pump station upgrades would be implemented in accordance with then-applicable permits, approvals, codes, and regulations.

2.6.1.2 Other Related Facilities

After the draft EIS was issued, plans were announced for future development of two projects that could transport crude oil to the proposed Project from producers in North Dakota and Montana and from producers in the Cushing, Oklahoma area. Those planned projects are the Bakken Marketlink Project and the Cushing Marketlink Project. Those projects are considered connected actions for the purpose of the EIS and are described using all available information in Sections 2.5.3 and 2.5.4.

2.6.2 Decommissioning of the Proposed Project

Many commenters requested that the EIS provide additional information about the anticipated life of the proposed Project and a description of how the proposed Project would be decommissioned at the end of its useful life. This section has been revised in response to those requests.

2.6.2.1 Project Life

Keystone used a design life of 50 years to develop the engineering standards for the proposed Project. However, with implementation of the pipeline integrity management plan, the 57 Project-specific Special Conditions developed by PHMSA (see Appendix U), and an operations and maintenance program as described above, Keystone anticipates that the life of the proposed Project would be much longer. Many other pipeline companies have safely extended the duration of pipeline systems by replacing sections of pipe after finding anomalies and by replacing or upgrading equipment and facilities at pump stations. As a result, it is not possible to identify a specific number of years that the proposed Project may be in service.

2.6.2.2 Decommissioning

PHMSA has requirements that apply to the decommissioning of crude oil pipelines in 49 CFR Section 195.402(c)(10) and in 49 CFR 195.59 and 195.402. These regulations require that for hazardous liquid pipelines, the procedural manuals for operations, maintenance, and emergencies must include procedures for abandonment, including safe disconnection from an operating pipeline system, purging of combustibles, and sealing abandoned facilities left in place to minimize safety and environmental hazards (49 CFR 195.402). Further, these regulations require that for each abandoned onshore pipeline facility that crosses over, under, or through a commercially navigable waterway, the last operator of that facility must file a report upon abandonment of that facility. It further states that “. . . operators must submit the date of abandonment, diameter, method of abandonment, and certification that, to the best of the operator's knowledge, all of the reasonably available information requested was provided and, to the best of the operator's knowledge, the abandonment was completed in accordance with applicable laws . . . The information in the report must contain all reasonably available information related to the facility,

including information in the possession of a third party. The report must contain the location, size, date, method of abandonment, and a certification that the facility has been abandoned in accordance with all applicable laws.”

TransCanada (the parent company of Keystone) would adopt operating procedures to address these requirements for the proposed Project as they have for previous pipeline projects including the existing Keystone Pipeline. TransCanada typically does not abandon large diameter pipelines but generally idles or deactivates pipe as market conditions dictate. This allows a dormant pipeline to be reactivated or converted to another purpose in the future. When a pipeline or a segment of a pipeline is idled or deactivated, the pipe generally is purged of its contents, filed with an inert gas, and left in place with warning signage intact. Cathodic protection would likely be left functional as would other integrity measures such as periodic inspections under the integrity management plan.

The proposed Project pipeline would traverse approximately 44.6 miles of federal land under the management and jurisdiction of the BLM. The majority of the federal land is in the state of Montana. The portion of the proposed Project that would cross BLM-administered land would be subject to the pipeline decommissioning and abandonment requirements stipulated in the BLM right-of-way grants and permanent easement permits. These requirements are:

- “1. Boundary adjustments in Oil and Gas [user entry (lease or unit number)] shall automatically amend this right-of-way to include that portion of the facility no longer contained within the above described [user entry]. In the event an automatic amendment to this right-of way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.
2. Prior to termination of the right-of-way, the holder shall contact the authorized officer to arrange a predetermination conference. This conference will be held to review the termination provisions of the grant.
3. [user entry, period of time] prior to termination of the right-of-way, the holder shall contact the authorized officer to arrange a joint inspection of the right-of-way. This inspection will be held to agree to an acceptable termination (and rehabilitation) plan. This plan shall include, but is not limited to, removal of facilities, drainage structures, or surface material, recontouring, topsoiling, or seeding. The authorized officer must approve the plan in writing prior to the holder’s commencement of any termination activities.”

The right-of-way (ROW) grant on federal lands under the management of BLM for the proposed Project would have a maximum term not to exceed of 30 years. For the proposed Project to extend beyond 30 years, the approved ROW grant would require a renewal authorization-certification decision by BLM. This decision would be considered a federal action subject to the requirements of NEPA. As a result, a decision to renew-certify the ROW grant to allow the proposed Project lifetime to remain in place beyond 30 years would be accompanied by an environmental analysis similar to the analysis required for the initial ROW grant. This process occurred on the Alyeska Oil Pipeline in Alaska. The initial ROW grant for federal lands crossed by that project extended from 1974 to 2004, and BLM and the State of Alaska through the Joint Pipeline Office required an EIS addressing continued operation of that project prior to certifying a new ROW grant with a maximum term of 30 years. It is likely that the future environmental assessment that would be required by BLM to renew-certify the approved ROW agreement grant for the proposed Project would include a review of the environmental effects of the continued operation of the entire proposed Project, since operations on non-federal lands would be connected actions to the renewal-

certification action on federal lands. Therefore, any operations or decommissioning that would occur beyond the initial 30-year ROW grant would be subject to extensive federal environmental review.

In Texas, Section 111.025 of the Texas Natural Resources Code would apply to decommissioning of the proposed Project. The provisions of the code are:

“(a) No common carrier may abandon any of its connections or lines except under authority of a permit granted by the commission or with written consent of the owner or duly authorized agent of the wells to which connections are made.

(b) Before granting a permit to abandon any connection, the commission shall issue proper notice and hold a hearing as provided by law.”

While there are no state regulations applicable to pipeline decommissioning in Montana, South Dakota, Nebraska, or Oklahoma, environmental specifications developed by Montana DEQ that would address reclamation of areas disturbed during abandonment would be a condition of the grant of a certificate under MFSA.

Decommissioning activities would have to be conducted consistent with all applicable regulatory requirements that are in place at the time of decommissioning. Since regulations at the federal, state, and local level change over time, it would be highly speculative to project what regulatory framework would apply to Project decommissioning at the end of the useful life of the proposed Project more than 50 years in the future.

Prior to decommissioning the Project, Keystone would identify the decommissioning procedures it would use along each portion of the route, identify the regulations it would be required to comply with, and submit applications for the appropriate environmental permits. At that point, Keystone and the issuing agencies would address the environmental impacts of implementation of the decommissioning procedures and identify the mitigation measures required to avoid or minimize impacts.

It is likely that after decommissioning there would be fewer land use restrictions than during operation of the proposed Project since either the ROW would no longer have strict encroachment limitations for protection of the purged pipeline, or the pipeline may have been removed and there would no longer be limitations of use of the former ROW.

As noted above, PHMSA regulations require that hazardous liquids pipelines be purged of combustibles prior to decommissioning. Therefore the potential for the release of contaminants from the decommissioned pipeline would be negligible.

2.7 REFERENCES

Accufacts, Inc. 2007. Recommended Leak Detection Methods for the Keystone Pipeline in the Vicinity of the Fordville Aquifer, September. Website (<http://www.psc.nd.gov/database/documents/06-0421/165-010.pdf>) accessed August 12, 2011.

Griesser, S. 2011. BakkenLink Pipeline LLC. Personal communication to Bill Staeger, Cardno ENTRIX, February, 2011.

PHMSA. See Pipeline and Hazardous Materials Safety Administration.

Pipeline and Hazardous Materials Safety Administration (PHMSA). 2007. Leak Detection Technology Study. As Required by The Pipeline Inspection, Protection, Enforcement and Safety (PIPES) Act of 2006 (Pub.L. No.109-468). December 31, 2007.

Purvin & Gertz. 2009. Western Canadian Crude Supply and Markets. A report prepared for TransCanada Keystone Pipeline GP LMTD.

This page intentionally left blank.